

ADDENDUM TO SCOPING REPORT

Ōtaki to North of Levin Expressway

Prepared for the NZ Transport Agency JULY 2012



This document has been prepared for the benefit of NZ Transport Agency. No liability is accepted by this company or any employee or sub-consultant of this company with respect to its use by any other person.

This disclaimer shall apply notwithstanding that the report may be made available to other persons for an application for permission or approval to fulfil a legal requirement.

QUALITY STATEMENT PROJECT MANAGER

Bob Barraclough

PROJECT TECHNICAL LEAD Phil Peet

PREPARED BY		
Phil Peet, Dhimantha Ranatunga, Stuart Woods CHECKED BY	· · · · · · · · · · · · · · · · · · ·	//
Bob Barraclough REVIEWED BY		//
Marten Oppenhuis APPROVED FOR ISSUE BY		/
Bob Barraclough		//

WELLINGTON

Level 1, 123 Taranaki Street, Wellington 6011 PO Box 9624, Te Aro, Wellington 6141 TEL +64 4 381 6700, FAX +64 4 381 6739

REVISION SCHEDULE

Rev	Data	Description	Signature Required				
No Date		Description	Prepared By	Checked By	Reviewed By	Approved By	
	Dec '12	Draft for Client	PP	BB	MO	BB	
A	July '12	Final	PP		BB	BB	



NZ Transport Agency

Ōtaki to North of Levin Expressway

CONTENTS

1	Intro	oduction	1
	1.1	Purpose of Study	1
	1.2	Purpose of Addendum Report	1
	1.3	Project Objectives	1
2	Sta	ging Options	2
	2.1	Contiguous Corridor 66	2
	2.2	Staging Options	2
3	Cos	t Estimates	5
4	Мос	delling	6
	4.1	Discussion	. 11
	4.2	Conclusion	. 12
5	Eco	nomic Evaluation	. 13
6	Con	clusions and Recommendations	. 17

LIST OF TABLES

Table 3-1 : Cost Estimates	5
Table 4-1 : Number of Vehicle Trips	6
Table 4-2 : Model Results	7
Table 4-3 : Relativity to Base Network – PM Peak period	7
Table 4-4 : Locations of poor Levels of Service – 2041	10
Table 4-5 : 2026 Traffic Volumes across Ohau River	10
Table 5-1: Travel Time Benefits	14
Table 5-2: Vehicle Operating Cost Savings and CO ₂ Benefits	14
Table 5-3: Crash Cost Benefits	15
Table 5-4: Economic Analysis Summary	15

LIST OF FIGURES

Figure 4-1: Vehicle Kilometres travelled in Model Area in Year 2016 runs	8
Figure 4-2: Vehicle Kilometres travelled in Model Area in Year 2041 runs	8
Figure 4-3: Total travel time in Model Area in Year 2016 runs	9
Figure 4-4: Total travel time in Model Area in Year 2041 runs	9



1 Introduction

1.1 **Purpose of Study**

The purpose of the study is to identify a preferred alignment for an expressway between north of Ōtaki and north of Levin and prepare applications for the required designation and resource consents.

The method being used to identify and secure the most suitable route for the expressway is the ACRE model: the acronym standing for Area, Corridor, Route, Easement. This is a systematic process utilising a range of "best practice" methods of identifying a preferred route option followed by refinement of that route, all in accordance with NZTA processes, consultation stages and reporting¹.

The Scoping Report was the first major deliverable for this study. It presented the methodology and outcomes to date in terms of identifying the preferred corridors with indicative routes.

The next stage is the scheme assessment, which will take the short list of corridors from the scoping report and develop them to a level of detail that, along with consultation outcomes, enables a preferred route to be chosen and hence designations and consents to be lodged.

1.2 Purpose of Addendum Report

After submission of the Scoping Report, the NZTA requested that investigation be undertaken into what possible staging opportunities would be available if a full four-lane expressway was unable to be implemented directly. Staging investigation was originally intended to form part of the Scheme Assessment phase; however, it was considered that some initial work was needed to assist in the upcoming public consultation process.

This report presents:

- the options being considered;
- the estimated cost of those options; and
- the economic evaluation of those options based on transportation modelling and crash analysis.

1.3 **Project Objectives**

At the time of preparing this report, the following project objectives apply to the Ōtaki to north of Levin expressway project:

- to provide a value for money proposal which will achieve the RoNS goals for this corridor of building a high quality expressway route between north of Ōtaki and north of Levin;
- to provide a better journey time Level of Service between north of Ōtaki and north of Levin;
- to reduce and progressively eliminate at-grade intersections between north of Ōtaki and north of Levin;
- to engage effectively with key stakeholders;
- to lodge Notices of Requirement and key resource consents with the appropriate consent authority by the 2012/13 financial year; and
- to improve safety on the route.

These project objectives will be refined as part of the on-going process of investigations.

¹ The ACRE process adopted for this study is explained in full in Section 7 of the Scoping Report



2 Staging Options

2.1 Contiguous Corridor 66

This report has not sought to determine which of the contiguous corridors recommended at the end of the scoping report should be developed further in the Scheme Assessment phase. However, one contiguous corridor has been picked to enable the analysis of staging options to be undertaken quickly and efficiently. Contiguous Corridor 66 has been chosen for two reasons:

- it facilitates staging opportunities to the south of Levin by remaining on one side of the existing railway lines (making it easier and cheaper to tie back into the existing SH1); and
- it facilities staging opportunities to the north of Levin by meeting the existing SH1 corridor in two separate locations (near Heatherlea East Road and near Oturoa Road).

2.2 Staging Options

During a meeting (25 October 2011) with NZTA and MWH representatives, it was determined that the following staging options would be considered as part of the addendum report.

- A two-lane access controlled route following the Contiguous Corridor 66 alignment (which could be upgraded to a full expressway at some point in the future)
- A 2+1 option comprising a median divided route with alternate passing lanes for a reduced length of the Contiguous Corridor 66 alignment (which could be upgraded to a full expressway at some point in the future)
- A three-stage option which progressively develops the full expressway.

In addition to the staging options above, it was requested that an expanded Do Minimum be developed which would resolve some of the significant safety issues on the existing state highway network.

These options are discussed in more detail below. Plans of the options are provided in Appendix A.

It is noted that each option has been evaluated separately. No attempt at this stage has been made to determine the benefits of implementing different scenarios at different time periods; e.g. Staging Option 3B is purely implementing all aspects of 3A and 3B in 2016 and leaving this in place until the end of the analysis period. The overall benefits of implementing 3A in 2016, 3B in 2026 and Contiguous Corridor 66 in 2036 has not been investigated.

2.2.1 Expanded Do Minimum

The Do Minimum presented in the original scoping report was essentially a Do Nothing as far as capital projects are concerned. If consideration is being given to staging or deferring the expressway then further consideration needs to be given to what projects would need to be undertaken.

Accordingly, this expanded Do Minimum comprises projects to address the safety issues that are present on the existing state highway network within the study area. It includes, from south to north:

- SH1 Forest Lakes Improvements. The preferred option (Option 2A) from the Forest Lakes Scoping Report (Contract 410PN, Beca, April 2010) comprises a wire rope median barrier within a 1.5 m median and widening to provide 2.0 m shoulders on either side of the carriageway between the Waitohu Stream Bridge and the Pukehou Rail Overbridge.
- SH1 Manukau Rail Overbridge. Replacement of this substandard rail overbridge to provide a safer alignment for state highway traffic.
- SH1 Ohau Rail Overbridge and River Bridge. Replacement of the substandard rail overbridge and a new crossing of the Ohau River to provide a safer alignment for state highway traffic.
- SH1 / SH57 Intersection Improvement. Upgrade the intersection to provide for the safe and efficient movement of all traffic. For example, install a rural roundabout.



- SH57 Kimberly Road / Arapaepae Road Intersection Improvement. Realignment of the highway to bypass the 90 degree turn at the current intersection.
- SH57 / Queen Street Intersection Improvement. Upgrade the intersection to provide for the safe and efficient movement of all traffic. For example, install a rural roundabout.
- SH1 in the vicinity of Waitarere Beach Road. Realign the highway through the three existing curves and three intersections to improve the safety of this stretch of highway.

The above improvements would address the top six blackspots as identified within the scoping report.

2.2.2 Option 2: Two Lane Route

This option comprises a two lane access controlled route on the alignment of Contiguous Corridor 66 from Taylors Road to the Manawatu River.

It would be a two lane, two way road with wire rope median barrier and at-grade intersections. Whilst the exact location and form of intersections has not been decided, they would be more regular than that for the full expressway. The route would be fully access controlled; however, there will be some locations where connectivity would be required across the new route. In these situations, access would be provided via local road intersections (cross or staggered T) rather than by overbridges or underpasses. Movements to and from Levin via Queen Street East would be provided for by a roundabout or other form of at-grade intersection.

This option allows for further stages in the upgrade to full expressway standard by constructing grade separated intersections and lengths of 4 lane expressway.

2.2.3 Option 3: Three Stage Option

Whilst the other options give two-stage approaches to developing the full expressway, this option involves three distinct phases.

2.2.3.1 Stage A – New 2 lane route south of Levin

This stage comprises:

- Forest Lakes Improvements (as per the Expanded Do Minimum)
- New 2 lane route from immediately south of the Pukehou Rail Overbridge to SH57 near the intersection of Kimberly Road and Arapaepae Road.
- Retaining the existing SH57 from Kimberly Road to north of Queen Street East but with a new roundabout at Queen Street East
- New 2 lane route from north of Queen Street to Heatherlea East Road on SH1.
- Retaining the existing SH1 from Heatherlea East Road to the Manawatu River.

The new sections of the highway would be access controlled. Intersections would be at-grade.

2.2.3.2 Stage B – 4 lane route south of Levin

This stage involves provision of the full expressway standard route from Taylors Road to Queen Street East. The expressway would rejoin the existing network at the Queen Street roundabout.

The section upgraded to four lanes would have all access removed and any local road crossings would be grade separated.

No changes would be implemented north of Queen Street East.

2.2.3.3 Stage C – Full expressway

The final stage would be to construct the four lane expressway north of Queen Street East so that the entire route is grade separated expressway from Taylors Road to the Manawatu River.



2.2.4 Option 4: 2+1 Option

A 2+1 road is a three lane road consisting of two lanes in one direction and one lane in the other, alternating every few kilometres. The opposing traffic flows are separated by a median with a wire rope safety barrier.

This option involves creating a 2+1 route from Taylors Road to Queen Street East and a new 2 lane link back to SH1 near Heatherlea East Road. This would result in a 2+1 facility south of Levin and a 2 lane plus passing lane facility north of Levin.

Safety improvements in the vicinity of Waitarere Beach Road would also be included to address the existing safety issue.

This route would be access controlled on all sections of new build. There will be some locations where connectivity would be required across the new route. In these situations, access via overbridges or underpasses would be considered so as to not interfere with safety or efficiency of the 2+1 operation.

Movements to and from Levin via Queen Street East would be provided for by a roundabout or other form of at-grade intersection.

This option allows for further stages in the upgrade to full expressway standard by constructing grade separated intersections and lengths of 4 lane expressway.



3 Cost Estimates

Estimates have been prepared in accordance with the NZTA Cost Estimation Manual for the expanded Do Minimum and the three staging options. As with the options in the scoping report, it is stressed that the information and data available is such that there is still a high level of uncertainty, and this is reflected in the 95% ile totals.

A summary of the costs is presented in Table 3-1 below. More detailed estimate information is found in Appendix B.

Do Min and Staging Option	Expected Estimate (\$M)	95%ile Estimate (\$M)
Expanded Do Minimum	56.4	80.8
2 Lane	380.3	545.5
Three Stage – Stage A	290.5	416.6
Three Stage – Stage B	101.2	145.2
Three Stage – Stage C	146.1	209.6
2+1 Option	338.2	485.0
Option 66 – Full Expressway	453.0	649.0

Table 3-1 : Cost Estimates

The costs are undiscounted and exclude escalation and GST.

The estimates have been undertaken as feasibility level estimates to provide costs for comparison purposes. Significant further work is necessary to refine these broad estimates during the Scheme Assessment stage of the project. Note that the 2 Lane and 2+1 lane option estimates do not include the costs of further upgrades to full expressway standards.

These cost estimates have been prepared on the same basis as the options in the Scoping Report. Accordingly, the estimates should be used in the knowledge of the assumptions, exclusions and methodologies outlined in Sections 13.1.2 to 13.1.6 of the Scoping Report.



4 Modelling

The same SATURN model was used for this staging network testing as was used for the earlier Otaki-Levin Scoping Study modelling. Thus the same basic road network and level of network detail has been used as the basis of the network coding for Option 66 staging options. The modelling for the base network and Option 66 has also been drawn upon for comparison purposes in the reporting of this additional modelling, but no further modelling of those options has been undertaken.

As with the options analysed in the Scoping Report, traffic modelling was undertaken for the current/dominimum road network and the staging options, assessing the morning peak (8.00-9.00 hrs), evening peak (16.30-17.30 hrs) and inter-peak (11.00-12.00 hrs) periods for the years 2016, 2026 and 2041.

The options have been appointed the following names for the modelling exercise:

- 2 lane option: S2
- 1st stage of the 3 Stage option: S3A
- 2nd stage of the 3 Stage option: S3B
- 2+1 option: S4

For each of the model runs for this testing (four networks for 2016, 2026 and 2041, all three periods), the following results are derived from the outputs and reported in this section:

- the summary statistics for Vehicle Kilometres Travelled and Total Travel Time; and
- Level of Service diagrams for 2016 and 2041, AM and PM peaks only

The numbers of vehicle trips in the modelled network for each period and year are shown in the table below. The trips are shown for both light vehicles and heavy vehicles, demonstrating the different growth rates between these classes. Perhaps mostly notable is the very low growth rate in trips, which is a result of the very low local growth rates in population and employment along with low and consistent slow growing state highway volumes as a proportion of the overall trip totals. The state highway light vehicle volumes are projected to grow at 1.5% per annum and heavy vehicles at 2.0% per annum.

	Number of Trips								
Year		AM Peak			nter Peak	۲.		PM Peak	
	LV	HV	Total	LV	HV	Total	LV	HV	Total
2011	6321	653	6973	5733	658	6391	7004	481	7485
2016	6390	661	7050	5786	669	6455	7076	489	7565
2026	6544	685	7230	5911	693	6604	7265	506	7771
2041	6776	729	7504	6086	729	6815	7525	533	8059

Table 4-1 : Number of Vehicle Trips

The outputs of modelling can be put to a range of purposes including evaluating the performance of the network, assessment of environmental effects (e.g. noise assessments), information for economic evaluations and data for road safety assessments. Results from this work have been key inputs to Benefit/Cost analysis of the staging options elsewhere in this report.

The global results (vehicle kilometres travelled and total travel time) of the network runs are presented in the tables and figures below. More extensive diagrams are provided in the appendices showing more detail on individual runs. Additionally the 2041 morning and evening peak hour runs Level of Service diagrams which indicate the levels of service for links and junctions are provided in Appendix C.



Table 4-2 : Model Results

Option	Output		2016			2041	
		AM	IP	PM	AM	IP	PM
Base	Total Travel Time	332.3	307.6	372.0	402.6	364.0	458.0
network	Total Distance Travelled	25517	23660	28455	31424	28525	35300
66	Total Travel Time	352.8	349.4	376.3	424.0	385.4	453.2
00	Total Distance Travelled	28120	26176	30388	34241	31279	37353
S2	Total Travel Time	329.4	309.7	364.2	394	362	441.8
	Total Distance Travelled	26386	24749	29523	32359	29678	36374
624	Total Travel Time	339.8	318.6	380.5	409.4	376.5	464.2
53A	Total Distance Travelled	26919	25276	30360	33398	30480	37823
620	Total Travel Time	326.4	305.9	359.6	389.0	357.4	432.2
99D	Total Distance Travelled	26292	24612	29439	32290	29575	36379
S 4	Total Travel Time	325.2	304.6	358.8	388.3	356.2	432.8
54	Total Distance Travelled	26127	24365	29170	32091	29322	36083

Table 4-2 above shows the overall statistics, with Table 4-3 below providing a summary of the evening peak hour travel time and total distance travelled for each of the staging options. This also shows the relative percentage of the option result compared to the base network. Further the colour coding of the cells indicates whether the staging option result shows a better or worse performance compared to Option 66.

		Base	66	S2	S3A	S3B	S 4
	2016	372.0	376.3	364.0	381.0	359.6	325.2
Total Travel Time	% of Base		101.2%	97.9%	102.3%	96.7%	87.4%
(Veh.hr/hr)	2041	458.0	453.2	442	464	432.2	432.8
	% of Base		98.9%	96.5%	101.4%	94.4%	94.5%
Total Distance	2016	28,455	30,388	29,523	30,360	29,439	29,170
Travelled	% of Base		106.8%	103.8%	106.7%	103.5%	102.5%
(Veh.km/hr)	2041	35,300	37,353	36,374	37,823	36,379	36,083
(% of Base		105.8%	103.0%	107.2%	103.1%	102.2%

Key: Green shading = better performance than Option 66 Red shading = worse performance than Option 66

The following four figures demonstrate graphically the vehicle kilometres travelled and the total travel time for the base network, Option 66 and the four staging options tested, for the 2016 and 2041 runs, grouped by period (morning, evening and inter-peak) to allow more direct comparison





Figure 4-1: Vehicle Kilometres travelled in Model Area in Year 2016 runs









Figure 4-3: Total travel time in Model Area in Year 2016 runs



Figure 4-4: Total travel time in Model Area in Year 2041 runs



Table 4-4 below summarises the locations from the staging network models where the level of service was D or worse. Only intersections showed up in these categories, with no links operating below level of service C.

Option	Level of Service	AM Peak	PM Peak
S2	D	 Expressway/South Manakau Rd (north end) Expressway/ next junction north of Sth Manakau 	 Expressway/Muhunoa East (both sides)
	E	 South Manakau Rd (south end)/SH1 	 Expressway/ next junction north of Sth Manakau South Manakau Rd (south end)/SH1
	F		South Manakau Rd (north end)/SH1
S3A	D	SH1/Bath StSH1/Forest Lakes Rd	SH1/Queen StKimberley/Arapaepae Rd
	E	 South Manakau Rd (south end)/SH1 	 South Manakau Rd (south end)/SH1 SH1/Kimberley SH1/Bath
	F		 SH1/Forest Lakes Rd
S3B	D		SH1/Queen St
	E	 South Manakau Rd (south end)/SH1 	 South Manakau Rd (south end)/SH1
	F		
S4	D	 SH1/Bath South Manakau Rd (north end)/SH1 SH1/Forest Lakes Rd 	
	E	 South Manakau Rd (south end)/SH1 	 South Manakau Rd (south end)/SH1
	F		South Manakau Rd (north end)/SH1SH1/Forest Lakes Rd

Table 4-4 : Locations of p	oor Levels of Service – 2041
----------------------------	------------------------------

Select link analysis was undertaken to determine the percentage of traffic that would be attracted to the new road / expressway in 2026. The table below outlines the traffic volumes estimated by the model for the staging options for a screenline at the Ohau River.

Table 4-5 : 2026 Traffic Volumes across Ohau River

Staging Option	Current SH1	New Road / Expressway		
Base Network	22,097	0		
Option 66	11,982	10,420		
2 Lane	10,186	12,216		
Three Stage – Stage A	5,081	17,317		
Three Stage – Stage B	10,530	11,872		
2+1 Option	11,149	11,253		



4.1 Discussion

The results presented of the staging network modelling runs have focussed on the 2016 and 2041 runs; the results of the 2026 runs are in between the results presented.

As with the original options modelling presented in the Scoping Report, there is an increase in network speed over the 30 year time period (2011-2041), which is a result of most of the growth in traffic in the model using the state highways, and thus pushing up the relative proportion of vehicles using higher speed roads which remain relatively uncongested.

The vehicle kilometres travelled modelling results of the four staging networks, as can be seen in the previous figures, are generally similar and almost all lie between the results for the base network and Option 66. The total travel time results for the staging options again are similar (although option S3A is consistently higher), and are consistently lower than the base network and Option 66.

As would be expected, the evening peak results are the overall highest values and inter-peak hour the lowest throughout the years modelled. The gap in result values grows between the periods over the years (e.g. the gaps between inter-peak and evening peak values are larger in 2041 than in 2016).

Option 66 performs worst of the sets of results presented here in all cases except for option S3A in travel time in 2016 and 2041, and VKT for year 2041 evening peak.

In all cases for Vehicle Kilometres Travelled, the base network results are the best over the years. For the same measure, Option 3A is consistently the worst performing of the 4 staging options, and in the evening peaks performs similarly to Option 66. For total travel time options S2, S3B and S4 start close to the base network results (and better for the evening peak period), and by 2041, these three options are showing growing travel time benefits over the base network (despite the longer distances of the new corridor/expressway). Option S3A is the worst performing of the 6 options presented for total travel time in both 2016 and 2041.

Overall from the perspective of both vehicle kilometres travelled and total travel time throughout the 2016-41 period, Option S4 could be considered the best alternative to the base network with Options S3B and S2 the second and third best options respectively.

The Level of Service analysis has been presented graphically in Appendix C for the 2041 morning and evening peak periods which are considered to represent the worst case situations for each network.²

As with the base network, the various staging options are shown to largely operate at acceptable levels of service with a small number of specific locations where further refinements and improvements of intersections may be required.

The figures in Appendix C show that all the mid-block road sections are operating at good levels of service. However, there are a number of intersections in the networks where the level of service has been assessed as D or worse (as noted in Table 4-4 above).

In all bar three cases, the poorly performing intersections are priority controlled junctions intersecting either with SH1 (current) or the new expressway (with at-grade intersections), and are in or south of Levin. At these locations, the poor performance is due to side road traffic seeking access to the main through route. Given the stage of development of the study, no iterative modelling has been done to seek to resolve these situations.

² Note: There is a graphical error in the diagrams for the Option S4 Level of Service, where the nodes for the proposed new links between Levin and Ohau have been incorrectly coded for their location (placing them to the west of SH1. However, the other characteristics of the associated nodes and links are correct, so this is a cosmetic error and does not affect the statistical results reported.



Two of the remaining locations that indicate poor future performance are the two signalised junctions in Levin, although neither is shown to be operating at LoS F. It is expected (from other assessments) that solutions could be found for these during option refinement.

In terms of the traffic attracted by the expressway, the model is estimating that Option 66 attracts less than half of the 2026 traffic that currently uses SH1 between Manakau and SH57. This is likely to be due to two reasons – the lack of connectivity to townships and local roads and the increased distance via the expressway to central Levin. As mentioned in the scoping report, further work will be done during the scheme assessment stage to increase the attractiveness of the expressway through consideration of interchange locations and alterations that are likely to happen to the existing state highway once it is bypassed. It is noted that with the increasing traffic volumes in future years, a much higher percentage of traffic is predicted to use the expressway in 2041.

Of the staging options, all have higher flows on the expressway than Contiguous Corridor 66. The most attractive option is Option 3A, likely due to its high level of connectivity to the local road network. However, the model results also show this option to be one with the highest number of vehicle kilometres travelled and total travel time.

4.2 Conclusion

The modelling undertaken of four staging network options has provided results related to vehicle kilometres travelled, total travel time and Levels of Service across the network.

This has shown that these networks on the whole perform better than Option 66, which was the starting point for developing these staging networks. This is principally due to the network not being congested to any notable degree in the base network option, in conjunction with the greater network connectivity of the staging options in contrast to the modelled network severance effects of the primary options such as Option 66.

In contrast to the full expressway options, the networks generally perform acceptably well and similar to or a little better than the base network.

Whilst the staging networks generally performed less well than the base network for vehicle kilometres travelled but better for total travel time, it is noteworthy that the total travel time results were showing a trend where the options were performing increasingly well in contrast to the base network and by 2041 three options had better total travel time statistics than the base network which may balance the increasing total distance travelled on the network. This infers a case for improvements with time, even if not being a strong case on modelling statistics in the early days.

Of the staging options tested, overall Option S4 (2+1 with limited new links, at-grade junctions) appears to perform the best with Options S3B (partial 4 lane motorway with other 2 lane new links) and S2 (2 lane expressway version of C66, at grade junctions) following in order, but it must be stressed that these options results are all close – within 1-2% generally of each other.



5 Economic Evaluation

Economic analysis was carried out in accordance with NZTA's Economic Evaluation Manual (EEM) using the outcomes of the SATURN transportation model.

The following assumptions have been made in the calculation of the Benefit Cost Ratio. They are:

- 1. The base year is 2011, time zero is 2012, start of construction 2016, start of (28 years) benefits 2018.
- 2. The travel time and vehicle operating costs have been calculated from the SATURN transportation modelling. The travel time benefits were determined by using the queuing delays and link cruise times, and the vehicle operating cost benefits determined from the fuel use output.
- 3. As presented earlier in this report, the model was run for the years 2011, 2016, 2026 and 2041 and for the AM, Interpeak and PM periods. The daily benefits were calculated by using an assessed number of hours per day for each time period. Annual costs were linearly interpolated between modelled years.
- 4. The accident costs have been calculated for the Do-Minimum network and each corridor option by splitting the network into multiple sections (and key intersections) to enable detailed analysis of crashes for the principal routes (SH1, SH57, Queen St and the option expressway).

Based on the Opus Peka Peka to Otaki model, the AADTs used in the accident analysis were estimated by applying factors of 2, 11.4 and 2 to the AM Peak, Inter-peak and PM Peak hour movement volumes, respectively.

The methods adopted for calculating the accident costs are summarised in the table below:

Method A: Accident by accident Method B: Accident rate analysis Method C: Weighted accident procedure

Section	Do min	Option
	Met	hod
Existing Highway	А	A, C
Proposed Expressway	-	В

- 5. No benefits associated with walking and cycling facilities, congestion reduction or driver frustration has been claimed. Furthermore, no wider economic benefits have been considered as these are being evaluated on the entire RoNS corridor.
- 6. Travel time benefits have been based on the Urban Arterial congested value of time applied to the total queuing delay, and a composite uncongested value of time applied to the link cruise times based on the urban/rural approximate split of 40/60 in travel demand from examination of the model link flows.
- 7. The VOC costs have been derived by applying the ratio of fuel to operating costs as given in the EEM for Rural Strategic. The CO₂ costs have been assessed as 4% of the VOC based on 10% heavy vehicles overall for the equations for light and heavy vehicles.
- 8. For the staging options, each has been evaluated separately for the entire period. No attempt at this stage has been made to determine the benefits of implementing different scenarios at different time periods; e.g. Staging Option 3B is purely implementing all aspects of 3A and 3B in 2016 and



leaving this in place until the end of the analysis period; the overall benefits of implementing 3A in 2016, 3B in 2026 and Contiguous Corridor 66 in 2036 has not been investigated.

A summary of the economic analysis is detailed in the following sections.

5.1.1 Travel Time Savings

The SATURN model outputs were used to determine the overall travel time values for each of the staging options. The travel time benefits and dis-benefits for each option, when compared to the Do-Minimum are shown below.

Note that this table compares to the Scoping Report Do Minimum not the Expanded Do Minimum.

Table 5-1: Travel Time Benefits

Option Description	Travel Time Savings (\$million)
Contiguous Corridor 66*	-19
Staging Option S2	1
Staging Option S3A	-6
Staging Option S3B	6
Staging Option S4 (2+1)	7
Expanded Do-Minimum	0

*Modelling updated compared to original option 66 in the Scoping Report

As with the model results presented earlier, the analysis shows that many of the staging options result in small travel time benefits due to the increase travel speed and connectivity with the local road network.

5.1.2 Vehicle Operating Cost Savings

The vehicle operating cost savings for each option, when compared to the Do-Minimum, are shown below. Carbon dioxide emission benefits are included in the numbers reported in the table.

Table 5-2: Vehicle Operating Cost Savings and CO₂ Benefits

Option Description	Vehicle Operating Cost and CO ₂ Savings (\$million)
Contiguous Corridor 66*	-20
Staging Option S2	-8
Staging Option S3A	-14
Staging Option S3B	-7
Staging Option S4 (2+1)	-5
Expanded Do-Minimum	0

*Modelling updated compared to original option 66 in the Scoping Report

Analysis of vehicle operating costs, based on fuel usage, shows that these are still negative which relates to the longer distance of the routes and the higher travel speeds.



5.1.3 Crash Cost Savings

The crash cost savings for each option, when compared to the Do-Minimum, are shown below.

Table 5-3: Crash Cost Benefits

Option Description	Crash Cost Savings (\$million)			
Contiguous Corridor 66	61			
Staging Option S2	87			
Staging Option S3A	55			
Staging Option S3B	56			
Staging Option S4 (2+1)	31			
Expanded Do-Minimum	14			

The crash analysis shows that Staging Option S2 provides higher crash cost benefits than the full expressway. This is primarily because the increased connectivity of the route attracts more traffic away from the old state highways onto the new safer road for the entire length of the corridor. The 2+1 option results in relatively poor crash cost savings because a high proportion of traffic stays on the old highways and it only provides the safer route for a proportion of the study length.

5.1.4 Option Costs

The pre-construction costs were estimated from the project feasibility estimates (December 2011). These project costs were discounted into the years at which the costs would occur. The project costs were discounted into the years that the element costs occurred. It was assumed that there would be an approximate 40 percent reduction in current maintenance costs for the existing SH1 and SH57 sections bypassed by the options. A uniform maintenance cost per km for the new route option was based on the annual maintenance costs in the latest Forward Works Program for SH1 and SH57 within the study area.

5.1.5 Benefit Cost Ratio Results

The benefit cost ratios for each option are shown below. The net present value (NPV) costs and benefits are also reported.

Table 5-4: Economic Analysis Summary

Option Description	NPV Costs (\$mill)	NPV Benefits (\$mill)	Benefit Cost Ratio
Contiguous Corridor 66*	294	21	0.07
Staging Option S2	244	80	0.33
Staging Option S3A	190	35	0.18
Staging Option S3B (includes S3A costs)	252	55	0.22
Staging Option S4 (2+1)	218	33	0.15
Expanded Do-Minimum	42	14	0.34

*Modelling updated compared to original Option 66 in the Scoping Report

The analysis shows that all options perform better than the full expressway.

As noted earlier in this section, each staging option has been evaluated separately for the entire analysis period. No attempt at this stage has been made to determine the benefits of implementing different



scenarios at different time periods; e.g. Staging Option 3B is purely implementing all aspects of 3A and 3B in 2016 and leaving this in place until the end of the analysis period; the overall benefits of implementing 3A in 2016, 3B in 2026 and Contiguous Corridor 66 in 2036 has not been investigated.

Benefit cost ratios are provided for comparative purposes and form an important part of the options assessment process. At this stage costs and benefits are uncertain and are likely to change significantly as the project develops and the scale and form of improvements are selected and refined.

It is noted that the assessment profile for the overall Wellington Northern Corridor RoNS is HHL.

This economic analysis has been subject to an external peer review with agreement reached between the analyst and the reviewer.

The economic analysis is detailed in Appendix D.



6 Conclusions and Recommendations

6.1 Discussion and Conclusions

Three staging options were considered as part of this addendum report.

- A two-lane access controlled route following the Contiguous Corridor 66 alignment (which could be upgraded to a full expressway at some point in the future)
- A 2+1 option comprising a median divided route with alternate passing lanes for a reduced length of the Contiguous Corridor 66 alignment (which could be upgraded to a full expressway at some point in the future)
- A three-stage option which progressively develops the full expressway.

In addition to the staging options identified above, an Expanded Do Minimum option was also developed as a potential staging option. This option essentially involves addressing some of the significant safety issues on the existing state highway network.

Each of the staging options assessed generally perform better than the four lane expressway for both vehicle kilometres travelled and total travel time due to the fact that the staging options have a larger number of connections with the local road network.

When comparing staging options to the existing road network, each still results in increased travel distances, but many of them have better network travel time with travel time benefits improving further in future years. However, due to the relatively high speeds already present on the existing state highway, the travel time benefits from the staging options are not considered to be materially significant. This reflects that fact that the Level of Service provided by the existing road network is considered to be adequate.

In terms of crash cost savings, many of the staging options capture the majority of the benefits that would be obtained by the full expressway. This is because the staging options will attract traffic away from the existing state highway network which suffers from various safety deficiencies.

In conclusion, staging is considered to be attractive when compared to constructing a full four lane expressway. This is particularly because each of the three options considered have lower capital costs and higher transport benefits compared to a full expressway.

However, given the capacity of the existing state highway is considered to be satisfactory for current and medium term demand, and as none of the options provide large travel time and/or vehicle operating benefits, improving the existing state highway route (i.e. the Expanded Do Minimum or similar) appears to be an attractive option. Further work would be needed to ensure the best treatments are being progressed and to determine whether other improvements such as passing lanes and wire rope barriers should be included. This Expanded Do Minimum approach should be considered as the first stage of a long term strategy for the upgrade of the state highway between Otaki and north of Levin. This option could realise cost effective safety benefits in the short to medium term prior to implementing any staged or full four lane option in the longer term.

6.2 Recommendations

There are two different approaches that the NZTA could adopt in order to progress its RoNS programme for the state highway network between north of Otaki and north of Levin.

If the desire is to construct a full four lane road in the short to medium term, it is recommended that further consideration and identification of layouts is undertaken to provide a range of opportunities for connection to existing settlements. This would involve iterative modelling to determine the most



beneficial staging methodology and final layout; i.e. consideration of 2+1 with local road connections as a staging option leading to a full four lane solution with a number of interchanges as an ultimate outcome.

If the desire is to proceed with the best value for money solution, it is recommended that further consideration be given to upgrading the existing state highway network along similar lines to the proposals included in the Expanded Do Minimum. If such an approach is pursued, it is recommended that it is considered to be the first stage of a long term strategy that may ultimately result in the section of highway between Otaki and Levin becoming a four lane road. Such an approach would allow the NZTA to realise important safety benefits in the short to medium term whilst deferring the need to construct four lanes for the time being.

Finally, it is recommended that further analysis be undertaken into the wider economic benefits of this project to enable the full range of benefits to be understood.



Appendix A Staging Option Plans





ALC AN	Otaki		Study Area
		++++++	Railway State highways Road Route
A A	Otaki to North of Levin Expressway	0 0.5 1	Corridor 2 3
NZ TRANSPORT AGENCY WARA KOTAHI	Scoping Report: Addendum Staging Options - Two Lane	Sc Origonal Map Siz Date: December 2 Appendix A	Kilometers cale: 1:90,000 e: A3 011 MWI

Waitarere Beach

Retain Existing (Two-Lane Highway with Passing Lanes)

Hokid

Hokio Beach

New Two-Lane Highway

Levin

Retain Existing Highway but Rationalise Intersections

Waikawa Beach New Two Lane Highway

Beach

Ν





		LEGEND
	Digki	Study Area Railway State highways Road Route Corridor
NZ TRANSPORT AGENCY WARA NOTAHI	Otaki to North of Levin Expressway Scoping Report: Addendum Staging Options - Stage 2 of 3 Ity available to NZTA and may change as further information becomes available, either internally, While all reasonable skill and care has been exercised in collating and presenting this y loss, damage, injury or expense (whether direct, indirect of consequential) arising out of the provision of this information or its use.	0 0.5 1 2 3 4 Kilometers Scale: 1:90,000 Origonal Map Size: A3 Date: December 2011 Appendix A



		LEGEND
	Digki	Study Area Railway State highways Road Route Corridor
NZ TRANSPORT AGENCY WARA NOTAHI	Otaki to North of Levin Expressway Scoping Report: Addendum Staging Options - Stage 2 of 3 Ity available to NZTA and may change as further information becomes available, either internally, While all reasonable skill and care has been exercised in collating and presenting this y loss, damage, injury or expense (whether direct, indirect of consequential) arising out of the provision of this information or its use.	0 0.5 1 2 3 4 Kilometers Scale: 1:90,000 Origonal Map Size: A3 Date: December 2011 Appendix A

Waitarere Beach

Retain Existing (Two-Lane Highway with Passing Lanes)

Hokio Beach

Hokio Stre

New Two-Lane Highway

Ohau

Levin

Retain Existing Highway but Rationalise Intersections and Widen to 2 + 1

Waikawa Beach

Beach

N

New 2 + 1 Alignment

		LEGEND
MA A	Otaki	Study Area
		Herein Hailway State highways Road Route Corridor
NZ TRANSPORT AGENCY	Otaki to North of Levin Expressway Scoping Report: Addendum Staging Options - 2+1 Alignment	0 0.5 1 2 3 4 Kilometers Scale: 1:90,000 Origonal Map Size: A3 Date: December 2011
This map is based on the information curren information, MWH accepts no liability for an	ty available to NZTA and may change as turther information becomes available, either internally or externally. While all reasonable skill and care has been exercised in collating and presenting this loss, damage, injury or expense (whether direct, indirect of consequential) arising out of the provision of this information or its use.	Appendix A



	Otaki	
	Otaki to North of Levin Expressway Scoping Report: Addendum Appendix A: Staging Options - Do Minimum	0 0.5 1 2 3 4 Kilometers Scale: 1:90,000 Origonal Map Size: A3
This map is based on the information currer information, MWH accepts no liability for an	tly available to NZTA and may change as further information becomes available, either internally or externally. While all reasonable skill and care has been exercised in collating and presenting this y loss, damage, injury or expense (whether direct, indirect of consequential) arising out of the provision of this information or its use.	Date: December 2011



Appendix B Cost Estimates

		-		Proje	ect Estima	ite				
	E,									
	FU	JIIIA			(3				
Project N	lame: Otaki to Levin Expressway RoNS Su	ımmary Base								
estimate	66 NE2:SE3									Facal dity activate
	-		increase in the second	Company of Company of Company		-			And the owner of the owner of the	reasibility estimate
ltem	Description		Base Estimate 66 NE2:SE3	Staged Sum Options 3A 3B 3C	Expanded Do Minimum Option 1	2 lane Option 2	4 Iane Stage 1 Option 3A	4 lane Stage 1 Option 3B	4 Iane Stage 1 Option 3C	2+1 lane Option 4
A	Nett project property cost		61,748,000.00	66,948,000.00	4,980,000.00	61,748,000.00	61,748,000.00	2,600,000.00	2,600,000.00	59,348,000.00
True To	Investigation and reporting:									-
	- consultancy fees			1					1	
D	- the NZTA-managed costs	tina	5 553 750 00	12 084 375 00	4 553 750 00	5 552 750 00	5 553 750 00	2 765 312 50	3 765 312 50	5 553 750 00
D	Design and project documentation:	ung	5,555,750.00	13,004,373.00	4,333,730.00	5,555,750.00	3,333,730.00	3,703,312.30	3,703,312.30	5,555,750.00
	- consultancy fees		1		131	T				
-	- the NZTA-managed costs		00 400 000 00	00,000,000,00	0.700.000.00	00 000 000 00	17 100 000 00	7 000 000 00	10,000,000,00	00 400 000 00
C	Construction	umentation	26,100,000.00	36,900,000.00	2,760,000.00	22,800,000.00	17,400,000.00	7,200,000.00	12,300,000.00	20,400,000.00
	MSQA	-								
1.0.0	- consultancy fees)(1.				() () () () () () () () () ()	1
1.0	- the NZIA-managed costs	-		()				-		
	Sub-total base MSQA			1	1					
	Physical works									
	1 Environmental compliance 2 Earthworks		5,140,333.28	6,353,541.55	280,606.80	5,140,333.28	3,709,984.07	1,220,299.37	1,423,258.11	4,505,437.24
	3 Ground improvements		1,879,000.00	1,879,000.00	33,840.00	1,127,400.00	751,600.00	751600.00	375,800.00	751,600.00
	4 Drainage		6,829,648.88	7,596,616.58	0	6,662,869.30	5,124,601.00	509,747.65	1,962,267.93	5,051,819.64
	6 Bridges ori	-	29 755 315 24	100,181,863.00	3,868,099.20	10 948 346 20	45,724,735.00	23,928,132.00	30,528,996.00	57,933,133.00
	7 Retaining walls		44,550.00	44,550.00	44,550.00	44,500.00	10,000,400.00	0,104,200.00	44,550.00	44,550.00
	8 Traffic services		12,628,159.47	17,913,421.69	2,383,667.16	18,265,347.46	10,705,853.60	2,884,585.14	4,322,982.95	13,142,480.07
1	9 Service relocations		7 814 646 78	990,000.00	55,000.00	330,000.00	4 826 700 00	330,000.00	330,000.00	440,000.00 5 701 186 44
1	1 Traffic management and temporary works	3	565,400.00	1,379,400.00	434,500.00	565,400.00	565,400.00	407,000.00	407,000.00	565,400.00
1	2 Preliminary and general		31,350,000.00	44,550,000.00	3,938,000.00	28,875,000.00	21,450,000.00	9,900,000.00	13,200,000.00	26,400,000.00
	Sub-total base physical works		13,405,972.69	18,161,487.07	817,339.60	10,968,602.43	6,290,388.86	6,111,483.03	5,759,615.18	11,4/6,7/3.17
D	Total construction		236,801,435.46	278,526,884.92	23,384,343.67	189,566,396.11	128,878,301.06	60,874,194.52	88,774,389.34	163,350,178.15
E	Project base estimate	(A+B+C+	330,203,185.46	395,459,259.92	35,678,093.67	279,668,146.11	213,580,051.06	74,439,507.02	107,439,701.84	248,651,928.15
F.	Contingency (Assessed/Analysed)	(A+B+C+D)	120,120,077	142,365,334	20,673,692	100,680,533	76,888,818	26,798,223	38,678,293	89,514,694
G	Project expected estimate	(E+F)	450,323,263	537,824,593	56,351,785	380,348,679	290,468,869	101,237,730	146,117,995	338,166,622
Project p	operty cost expected estimate									
Design a	and project documentation expected estimate									
Construc	ion expected estimate									
Н	Funding risk (Assessed/Analysed)		195,527,348	233,519,841	24,467,568	165,144,852	126,119,640	43,956,745	63,443,456	146,829,685
L.	95th percentile project estimate		645,850,611	771,344,434	80,819,354	545,493,531	416,588,510	145,194,475	209,561,450	484,996,308
Project p	operty cost 95th percentile estimate									
Investiga Docian	tion and reporting 95th percentile estimate	nato								
Construct	tion 95th percentile estimate	nate								
Sonoudo	and seat percenting continues									
100 million (1990)	Autoritation -									

Date of estimate	Cost index (Qtr/Year)
Estimate prepared by Chris Bremner	Signed
Estimate internal peer review by Bob Barraclough	Signed
Estimate external peer review by	Signed
Estimate accepted by the NZTA	Signed

Note: (1) These estimates are exclusive of escalation and GST.

THE NZ TRANSPORT AGENCY Ōtaki to North of Levin Expressway



Appendix C SATURN Level of Service Diagrams



S2 2041 AM Peak





S2 2041 PM Peak





S3A 2041 AM Peak





S3A 2041 PM Peak





S3B 2041 AM Peak





S3B 2041 PM Peak





S4 2041 AM Peak





S4 2041 PM Peak





Appendix D Economic Evaluation Worksheets



GENERAL ROADING IMPROVEMENT WORKS: EVALUATION SUMMARY

1	Evaluator(s) Dhimantha Ranatunga				
Reviewer(s) David Wanty					
2	Project / Package Details Approved Organisation Name Project / Package Name Your Reference Project Description Describe the problem to be addressed	MWH (NZ) Ltd Otaki to Levin RoNS Otaki to Levin RoNS Levin Bypass			
3	Location Brief description of location SH1 and S	H57 north of Otaki to north o	of Levin		
4	Alternatives and Options Describe the Do Minimum Reta	ain existing state highway			
	Summarise the options assessed Levi	n Bypass Option 66			
5	Timing Time Zero Assumed construction start date) Expected duration of construction (Mon	1 July 20 1 July 20 1 24 mon	012 018 ths		
6	Economic Efficiency Date economic evaluation completed (n Base date for costs AADT at Time Zero (SH1 Taylors Rd) Traffic Growth Rate at Time Zero (%)	nm/yyyy) 27 Septemb 1 July 20 9,000 1.5%	Existing Traffic Speed	50-100 km/br	
	Predicted Roughness 3 Affected SH1 before improvements Affected SH57 and Queen St (W / E) Bypass total sectional length:	IRI or NAASRA 30.600 km 17.500 km 32.650 km	Predicted Traffic Speed Posted Speed Limit Road Type Gradient Before Improve Gradient After Improve	300 100 km/hr 50-100 km/hr 50-100 km/hr vements 0% ments 0%	
7	PV Cost of Do Minimum		Cost \$	\$5,851,150 A	
8	PV Cost of the preferred Option		Cost \$	\$299,797,694 B	
9	Benefit values from Worksheet 4, 5 o PV Travel Time Cost savings: \$\$	r 6 14,530,135 C x Update	Factor [™] 1.3	<mark>3 = \$\$19,325,079 _</mark> ₩	
	PV VOC & CO2 savings: \$\$	19,437,913 D x Update	Factor ^{VOC} 1.0	4 = \$\$20,215,429 Y	
	PV Accident Cost savings: \$	51,901,878 E x Update	Factor ^{AC}	7 = \$ \$60,725,197 Z	
10	B/C Ratio = <u>W + Y + Z</u> = <u>BEN</u> B - A CC	<u>IEFITS</u> = <u>-19325079 + -</u> DSTS 29979	<u>20215429 + 60725197</u> 7694 - 5851150	= 0.07	
11	FYRR = <u>1st Year BENEFITS</u> = COSTS TTC year 1 benefits (Mid Year \$ (Mid Year 6.5 discounted) VOC & CO2 year 1 savings: \$ (Mid Year 6.5 discounted)	43 299797 31,120,122 51,391,648	<u>76905.94</u> 694 - 5851150	= 1.5%	
	2011 annunal AXS \$_\$	6,888,676			



GENERAL ROADING IMPROVEMENT WORKS: EVALUATION SUMMARY

1	Evaluator(s) Dhimantha Ranatunga, Ian Robertson Reviewer(s) David Wanty				
2	Project / Package Details Project / Package Name Your Reference Project Description Describe the problem to be addressed	Otaki to Levin RoNS Otaki to Levin RoNS Levin Bypass			
3	Location Brief description of location SH1 and SH57 north of Otaki to north of Levin				
4	Alternatives and Options Describe the Do Minimum Retain Summarize the options assessed Stage	n existing state highway			
5	Timing				
U	Time Zero Assumed construction start date) Expected duration of construction (Month	1 July 20 1 July 20 1s) 24 mon	012 018 ths		
6	Economic Efficiency Date economic evaluation completed (m Base date for costs AADT at Time Zero (SH1 Taylors Rd) Traffic Growth Rate at Time Zero (%)	m/yyyy) 27 Septemb 1 July 20 9,000 1.5%	er 2011 012		
	Existing Roughness Predicted Roughness Affected SH1 before improvements Affected SH57 and Queen St (W / E) Bypass total sectional length:	20 IRI or NAASRA 20 IRI or NAASRA 25.075 km 16.700 km 28.516 km	Existing Traffic S Predicted Traffic Posted Speed Li Road Type Gradient Before Gradient After In	Speed50-100Speed50-100mit50-100Juprovements50-100	km/hr km/hr km/hr 0%
7	PV Cost of Do Minimum		Cost \$	\$5,851,150	Α
8	PV Cost of the preferred Option		Cost \$	\$249,932,18	<u>4</u> B
9	Benefit values from Worksheet 4, 5 or PV Travel Time Cost savings: \$\$1	6 ,086,642 C x Update	Factor [™]	1.33 = \$	\$1,445,234 W
	PV VOC & CO2 savings: \$\$7	7,693,560 D x Update	Factor ^{VOC}	1.04 = \$	-\$8,001,302 Y
	PV Accident Cost savings: \$ \$7	3,985,855 E x Update	Factor ^{AC}	1.17 = \$	\$86,563,451 Z
10	$B/C \text{ Ratio} = \frac{W + Y + Z}{B - A} = \frac{BENE}{COS}$	<u>EFITS</u> = <u>1445234 + -</u> STS 24993	<u>8001302 + 86563</u> 2184 - 5851150	<u>451</u> =	0.33
11	FYRR = <u>1st Year BENEFITS</u> = COSTS	<u>29</u> 249932	<u>03296.63</u> 184 - 5851150		= 1.19%



GENERAL ROADING IMPROVEMENT WORKS: EVALUATION SUMMARY

1	Evaluator(s)Dhimantha RanatungaReviewer(s)David Wanty				
2	Project / Package Details Project / Package Name Your Reference Project Description Describe the problem to be addressed	Otaki to Levin RoNS Otaki to Levin RoNS Levin Bypass			
3	Location Brief description of location SH1 and SH57 north of Otaki to north of Levin				
4	Alternatives and Options Describe the Do Minimum Reta	in existing state highway			
	Summarise the options assessed Stag	ing Option S3A			
5	Timing Time Zero Assumed construction start date Expected duration of construction (Mont	<u>1 July 20</u> <u>1 July 20</u> ths) <u>24 mont</u>	012 018 hs		
6	Economic Efficiency Date economic evaluation completed (n Base date for costs AADT at Time Zero (SH1 Taylors Rd) Traffic Growth Rate at Time Zero (%)	nm/yyyy) 27 September 1 July 20 9,000 1.5%	er 2011 112		
Existing Roughness3.20IRI or NAASRAExisting Traffic Speed50-100Predicted Roughness3.20IRI or NAASRAPredicted Traffic Speed50-100Affected SH1 before improvements25.075kmPosted Speed Limit50-100Affected SH57 and Queen St (W / E)16.700kmRoad TypeBypass total sectional length:20.043kmGradient Before Improvements				km/hr km/hr km/hr 0%	
7	PV Cost of Do Minimum		Cost \$	\$5,851,150	A
8	PV Cost of the preferred Option		Cost \$	\$196,224,31	<u>3</u> B
9	Benefit values from Worksheet 4, 5 o PV Travel Time Cost savings: \$\$	r 6 4,644,712 C x Update I	Factor [™]	1.33 = \$	-\$6,177,467 W
	PV VOC & CO2 savings: \$\$1	13,106,179 D x Update F	=actor ^{voc}	1.04 = \$	-\$13,630,426 Y
	PV Accident Cost savings: \$ \$4	6,736,363 E x Update F	Factor ^{AC}	1.17 = \$	\$54,681,545 Z
10	$B/C \text{ Ratio} = \frac{W + Y + Z}{B - A} = \frac{BEN}{CO}$	<u>EFITS</u> = <u>-6177467 + -1</u> STS 196224	<u>13630426 + 5468⁻</u> 4313 - 5851150	1545 =	0.18
11	FYRR = <u>1st Year BENEFITS</u> = COSTS	<u>-27</u> 196224	<u>19879.61</u> 313 - 5851150		= -1.43%



GENERAL ROADING IMPROVEMENT WORKS: EVALUATION SUMMARY

1	Evaluator(s) Dhimantha Ranatunga, Ian Robertson Reviewer(s) David Wanty				
2	Project / Package Details Project / Package Name Your Reference Project Description Describe the problem to be addresse	Otaki to Levin RoNS Otaki to Levin RoNS ed Levin Bypass			
3	Location Brief description of location SH1 and SH57 north of Otaki to north of Levin				
4	Alternatives and Options Describe the Do Minimum F	Retain existing state highway			
	Summarise the options assessed	Staging Option S3B			
5	Timing Time Zero Assumed construction start date) Expected duration of construction (M	1 July 20 1 July 20 1 July 20 24 months)	012 018 ths		
6Economic EfficiencyDate economic evaluation completed (mm/yyyy)27 September 2011Base date for costs1 July 2012AADT at Time Zero (SH1 Taylors Rd)9,000Traffic Growth Rate at Time Zero (%)1.5%					
	Existing Roughness Predicted Roughness Affected SH1 before improvements Affected SH57 and Queen St (W / E Bypass total sectional length:	3.20 IRI or NAASRA 3.20 IRI or NAASRA 25.075 km 16.700 km 20.043 km	Existing Traffic S Predicted Traffic Posted Speed Lir Road Type Gradient Before I Gradient After Im	beed 50-100 Speed 50-100 nit 50-100 mprovements provements	km/hr km/hr km/hr <mark>0%</mark> 0%
7	PV Cost of Do Minimum		Cost \$	\$5,851,150	Α
8	PV Cost of the preferred Option		Cost \$	\$257,974,313	<u>3</u> B
9	Benefit values from Worksheet 4, PV Travel Time Cost savings: \$ PV VOC & CO2 savings: \$ PV Accident Cost savings: \$	5 or 6 <u>\$4,255,734</u> C x Update <u>-\$6,894,088</u> D x Update <u>\$48,098,994</u> E x Update	Factor [™] Factor ^{voc} Factor ^{AC}	1.33 = \$ 1.04 = \$ 1.17 = \$	\$5,660,126 W -\$7,169,852 Y \$56,275,823 Z
10	B/C Ratio = <u>W + Y + Z</u> = <u>B</u> B - A	<u>ENEFITS</u> = <u>5660126 + -</u> COSTS 257974	<u>7169852 + 562758</u> 4313 - 5851150	23 =	0.22
11	FYRR = <u>1st Year BENEFITS</u> = COSTS	<u>81</u> 257974	1 <u>8703.73</u> 313 - 5851150		= 0.32%



GENERAL ROADING IMPROVEMENT WORKS: EVALUATION SUMMARY

1	Evaluator(s)Dhimantha RanatungaReviewer(s)David Wanty				
2	Project / Package Details Project / Package Name Your Reference Project Description Describe the problem to be addressed	Otaki to Levin RoNS Otaki to Levin RoNS Levin Bypass			
3	Location Brief description of location SH1 and SH	157 north of Otaki to north o	of Levin		
4	Alternatives and Options Describe the Do Minimum Retain Summarise the options assessed Levin	n existing state highway Bypass Option S4 2+1			
5	Timing Time Zero Assumed construction start date) Expected duration of construction (Month	<u>1 July 20</u> <u>1 July 20</u> 1 July 20 1s) <u>24 mont</u>	012 018 hs		
6	Economic Efficiency Date economic evaluation completed (mi Base date for costs AADT at Time Zero (SH1 Taylors Rd) Traffic Growth Rate at Time Zero (%)	m/yyyy) 27 Septembe 1 July 20 9,000 1.5%	er 2011 012		
Existing Roughness3.20IRI or NAASRAExisting Traffic SpeedPredicted Roughness3.20IRI or NAASRAPredicted Traffic SpeedAffected SH1 before improvements25.075kmPosted Speed LimitAffected SH57 and Queen St (W / E)16.700kmRoad TypeBypass total sectional length:17.087kmGradient Before Improve				peed 50-100 Speed 50-100 mit 50-100 mprovements provements	km/hr km/hr km/hr 0%
7	PV Cost of Do Minimum		Cost \$	\$5,851,150	Α
8	PV Cost of the preferred Option		Cost \$	\$223,353,79	0 B
9	Benefit values from Worksheet 4, 5 orPV Travel Time Cost savings:\$5PV VOC & CO2 savings:\$ -\$5	6 <u>177,928</u> C x Update I ,264,914 D x Update I	[∓] actor [™]	1.33 = \$ 1.04 = \$	\$6,886,644 W -\$5,475,511 Y
	PV Accident Cost savings: \$ \$26	6,710,297 E x Update F	⁼ actor ^{AC}	1.17 = \$	\$31,251,048 Z
10	B/C Ratio = <u>W + Y + Z</u> = <u>BENE</u> B - A COS	<u>FITS = 6886644 + -</u> STS 223350	5475511 + 31251(3790 - 5851150	048 =	0.15
11	FYRR = <u>1st Year BENEFITS</u> = COSTS	<u>-5(</u> 223353 ⁻	<u>09038.34</u> 790 - 5851150		= -0.23%



GENERAL ROADING IMPROVEMENT WORKS: EVALUATION SUMMARY

1	Evaluator(s) Dhimantha Ranatunga					
	Reviewer(s) David Wanty					
2	Project / Package Details Project / Package Name Your Reference Project Description Describe the problem to be addressed	Otaki to Levin RoNS Otaki to Levin RoNS Levin Bypass				
3	Brief description of location SH1 and SH57 north of Otaki to north of Levin					
4	Alternatives and Options Describe the Do Minimum Retain existing state highway					
	Summarise the options assessed Cras	h improvements on Existing	g do-min			
5	Timing Time Zero Assumed construction start date) Expected duration of construction (Mont	1 July 20 1 July 20 hs) 24 mont)12)18 hs			
6Economic EfficiencyDate economic evaluation completed (mm/yyyy)27 September 2011Base date for costs1 July 2012AADT at Time Zero (SH1 Taylors Rd)9,000Traffic Growth Rate at Time Zero (%)1.5%						
	Existing Roughness 3 Predicted Roughness 3 Affected SH1 before improvements Affected SH57 and Queen St (W / E) Bypass total sectional length:	20 IRI or NAASRA 20 IRI or NAASRA 25.075 km 16.700 km 0.000 km	Existing Traffic Spe Predicted Traffic Sp Posted Speed Limit Road Type Gradient Before Imp Gradient After Impre	ed 50-100 kr beed 50-100 kr t 50-100 kr provements ovements	n/hr n/hr n/hr 0%	
7	PV Cost of Do Minimum		Cost \$	\$0	Α	
8	PV Cost of the preferred Option		Cost \$	\$41,919,900	В	
9	Benefit values from Worksheet 4, 5 or PV Travel Time Cost savings: \$	r 6 \$0 C x Update I	Factor [™]	1.33 = \$	NIL W	
	PV VOC & CO2 savings: \$	\$0 D x Update I	Factor ^{voc}	1.04 = \$	NIL Y	
	PV Accident Cost savings: \$ \$1	2,128,063 E x Update I	Factor ^{AC}	1.17 = \$	5 14,189,833 Z	
10	$B/C \text{ Ratio} = \frac{W + Y + Z}{B - A} = \frac{BEN}{CO}$	<u>EFITS</u> = <u>0 + 0</u> STS 41	<u>) + 14189833</u> 919900 - 0	=	0.34	
11	FYRR = <u>1st Year BENEFITS</u> = COSTS	<u>33</u> 419	<u>35647.44</u> 119900 - 0	:	- 7.96%	