Traffic Control Devices Manual Part 8

Code of practice for temporary traffic management (CoPTTM)

manual number: SP/M/010

Section E

© NZ Transport Agency

www.nzta.govt.nz

Fourth edition, Amendment 4 of Code of practice for temporary traffic management

Date of issue: November 2018 Effective date: 1 February 2019 ISBN 978-0-478-40772-3 (print) ISBN 978-0-478-40773-0 (online)

Copyright information

This publication is copyright © NZ Transport Agency. Material in it may be reproduced for personal or in-house use without formal permission or charge, provided suitable acknowledgement is made to this publication and the NZ Transport Agency (NZTA) as the source. Requests and enquiries about the reproduction of material in this publication for any other purpose should be made to: NZ Transport Agency Private Bag 6995 Wellington 6141

The permission to reproduce material in this publication does not extend to any material for which the copyright is identified as being held by a third party. Authorisation to reproduce material belonging to a third party must be obtained from the copyright holder(s) concerned.

Disclaimer

The NZTA has endeavoured to ensure material in this document is technically accurate and reflects legal requirements. However, the document does not override governing legislation. The NZTA and its employees and agents involved in the preparation and publication of this document do not accept liability for any consequences arising from the use of this document. Users of this document should apply and rely upon their own skill and judgment, and should not rely on the manual's contents in isolation from other sources of advice and information. In applying their own skill and judgment, the standards of safety and serviceability explicitly required or implied by this manual shall not be reduced. If the user is unsure whether the material is correct, they should make direct reference to the relevant legislation or regulations and contact the NZTA.

More information

Published 2013

ISBN 978-0-478-40772-3 (print)

ISBN 978-0-478-40773-0 (online)

Section E - Standard forms and descriptions

E1 Appendix A: Traffic management plans	1
E1.1 General	1
E1.2 Example of traffic management plan (TMP) - short form	2
E1.3 Guidelines for completion of TMP - short form	5
E1.4 Example of TMP - full form	9
E1.5 Guidelines for completion of TMP - full form	16
E1.6 Example of on-site record	25
E1.7 Engineering exception decision	27
E1.8 Example of checking process for generic traffic management pl (TMPs)	ans 28
E1.9 Additional information about completion of traffic managemen plans (TMPs)	t 29
E1.10 Example of schedule of specific job requirements for traffic management and safety	30
E2 Appendix B: Temporary speed limit (TSL) decision matrix	
worksheet	31
E3 Appendix C: Procedures for safety audit/review of worksites	32
E3.1 Introduction	32
E3.2 TTM safety audit/review methodology	33
E3.3 SCR for full and short audit/review	34
E3.4 Sighting TMPs	35
E3.5 Actions following SCR	35
E3.6 Notice of non-conformance	38
E3.7 Example of site condition rating (SCR) form - full audit/review	40
E3.8 Full audit/review site condition rating (SCR) - defect description	ons 41
E3.9 Example of site condition rating (SCR) form - short audit	50
E3.10 Examples of ratings (short audit)	51
E4 Appendix D: Measure and payment for traffic management (guidelines only)	52
E5 Appendix E: Newspaper advertisement standard	53
E6 Appendix F: Example of notice of non-conformance	54
E7 Appendix G: Example of notification of road closure/lane closure of state highways/local authority road	e 55
E8 Appendix H: (Ex-LRS – only applies to STMS-delegated authority to self-approve) Example of application for delegated authority tapprove TMPs for selected level LV and level 1 roads	
E9 Appendix I: (Ex-LRS – only applies to STMS-delegated authority self-approve) Example of application for traffic management coordinator's (TMC) approval of traffic management plan (TMP)	
	57

E10 Appendix J: (Ex-LRS - only applies to STMS-delegated authorit	у
to self-approve) Database to record delegations to STMS	58
E11 Appendix K: Report on incident at roadworks site	59
E11.1 Appendix K: Guidelines for completion of Report on incident at roadworks site	62

E1 Appendix A: Traffic management plans

E1.1 General

There are two traffic management plan (TMP) forms. Each form has been designed for a specific use.

Type of form	When to use	Guidelines for completion
Example of traffic management plan (TMP) – short form	Complete short form if simple activity and the road controlling authority (RCA) allow use of the form.	Guidelines for completion of TMP - short form
Example of TMP - full form	Use full form for activities involving a number of phases and/or delays (eg resealing, shoulder widening, road reconstruction) and any activities as required by the RCA.	Guidelines for completion of TMP - full form

Word versions of each form are available from the NZ Transport Agency's (NZTA) website.

E1.2 Example of traffic management plan (TMP) - short form

RCA consent (e			nd/or										
TRAFFIC MA							Transpar	t Agon	ov'o Troffio	aantral de	viaca manu	l port	0 Codo
Complete short of practice for te												ıı, parı	8 Code
Organisation/		referenc	Ť	•	Vorking spac		Principal (Client):						
TMP reference			С	ontractor (T	TM):		RCA:						
		Road names and suburb						use no rom ar	. I RPs nd to)	Road level	Permanent speed		Γ/Peak ows
Location details and road													
characteristics	⊩												
Description of work activity													
Planned work p	orogramn	ne											
Sta	rt date			•	Time		End da	te			Time		
Consider signif stages, for exam road closure detours no activity periods.	nple:												
Alternative date activity delayed													
Road aspects a	affected (delete e	either Ye	es or No to sl	how which as	spects a	re affecte	ed)					
Pedestrians affe	ected?	Yes	No	Property ac	ccess affecte	ed?	Yes	No	Traffic	lanes affe	ected?	Yes	No
Cyclists affecte	d?	Yes	No	Restricted	parking affe	cted?	Yes	No	Delays	or queuir	ng likely?	Yes	No
TSL/ Diagram (see TSL decision matrix for guidance)	TSL details as required Approval of Temporary Speed Limits (TSL) are in terms of Section 6 of Land Transport Rule: Setting of Speed Limits 2017, Rule 54001/2017 (List speed, length and location)						Times From and	to)	Dat (Start an		Diagra i (Layout Ti		

Attended day/ night	is hereb the leng (House	•	nicles travelling of ed between House no./RP)						
Unattended day/ night	is herek the leng (House	mporary maximum speed limit of km/h ereby fixed for motor vehicles travelling over length of m situated between use no./RP) and (House no./RP) on (street or road name)							
TSL duration	Will the TSL be required for longer than 12 months? If yes, attach the completed checklist from section I-18: Guidance on TMP Monitoring Processes for TSLs to this TMP. Yes No								
Contingency pl	lan								
If long queues form or delays exceed 5mins (or any other period required by RCA), site to be disestablished or additional lanes made available. Adjust TMD to circumstances overlaps with a				s (eg weathe	r or s		Emergency ser accommodated through the site	d and access pro	ovided
Add additional	conting	jencies:							
Contact details	;								
		Name			24/7 contac	t CoPTTM		Expiry	
			name			number	ID	Qualification	date
Principal			name					Qualification	
Principal TMC			Name					Qualification	
-			Name					Qualification	
TMC Engineers'			Name					Qualification	
TMC Engineers' representative			Name					Qualification	
TMC Engineers' representative Contractor			Name					Qualification	
TMC Engineers' representative Contractor STMS	ired		Name					Qualification	
TMC Engineers' representative Contractor STMS TC Others as requ TMP preparation	on (or ap	oproval if STMS dele	egated authorit	•	e TM	number		Qualification	
TMC Engineers' representative Contractor STMS TC Others as requ TMP preparation	on (or ap	•	egated authorit	•	e TM	number		Qualification	
TMC Engineers' representative Contractor STMS TC Others as requ TMP preparation Delete the option	on (or ap	•	egated authorit	•	e TM	number		Qualification	
TMC Engineers' representative Contractor STMS TC Others as requ TMP preparation Delete the option Prepared / App	on (or ap n that do	pes not apply (either p	egated authorit	roved)		Ps) Signature	ID		date
TMC Engineers' representative Contractor STMS TC Others as requ TMP preparation Delete the option Prepared / App	on (or ap	oes not apply (either p	egated authorit	roved)		Ps) Signature	ID I		date

Engineer/TMC to complete following section when approval or acceptance required										
Approved by TMC or engineer										
(delete one)	Name	Date	Signature	ID no.	Qualification	Expiry date				
Acceptance by TMC (only required if TMP approved by										
engineer)	Name	Date	Signature	ID no.	Qualification	Expiry date				

Qualifier for engineer or TMC approval

Approval of this TMP authorises the use of any regulatory signs included in the TMP or attached traffic management diagrams.

This TMP is approved on the following basis:

- 1. To the best of the approving engineer's/TMC's judgment this TMP conforms to the requirements of CoPTTM.
- 2. This plan is approved on the basis that the activity, the location and the road environment have been correctly represented by the applicant. Any inaccuracy in the portrayal of this information is the responsibility of the applicant.
- 3. The TMP provides so far as is reasonably practicable, a safe and fit for purpose TTM system.
- 4. The STMS for the activity is reminded that it is the STMS's duty to postpone, cancel or modify operations due to the adverse traffic, weather or other conditions that affect the safety of this site.

E1.3 Guidelines for completion of TMP - short form

RCA consent (eg CAR/WAP) and/or RCA contract reference

Add the appropriate RCA consent reference, for example the corridor access request (CAR) or work access permit (WAP) and/or any RCA contract reference.

TRAFFIC MAN	JAGEMENT P	I AN (TMP) -	SHOP	RT FORM						
Complete short for	orm if simple acti	vity and RCA pe	rmits. Re	efer to the NZ					al, part 8 Code	
Organisation/	TMP reference: Add the RCA's and	Contractor (V State the nai responsible t space	Norking me of th	space):	Principal (Client): State the name of the principal or client for this project (eg NZTA or Chorus)					
TMP reference	contractor's reference numbers	State the nar	ntractor (TTM): te the name of the contractor consible for the TTM					CA who cont ote: There ca	rols the road an be more	
	R	oad names and	l suburb		House n	o. / RPs and to)	Road level	Permanent speed	AADT/Peak flows	
Location details and road characteristics	details and coad					Enter house numbers, route positions or power pole numbers where applicable		Enter highest permanent limit	Include AADT and/or peak hour and heavy vehicle counts where avail- able. The RCA or engineer must provide this information if available.	
	As above	As above					As above	As above	As above	
	As above	As above		As above	As above	As above				
Description of work activity	identify if the a management	ee the main wol activity will affe diagrams.								
Planned work pro	ogramme									
Start	date Enter ea activity n	rliest date nay start	Time	Enter earliest time activity may start	End date	Enter late activity m allowing t unforesee	ay finish or	Time	Enter latest time activity may finish allowing for unforeseen issues	

Consider signi stages, for exal road closur detours no activity periods.	mple:										
Alternative dat activity delaye	LEOF LORGER OCTIVITIES IMENTITY ONLY OLIGINATIVE ROLES THAT CAN BE SCHEMILIED IT THE WORK IS DELIVED.										
Road aspects affected (delete either Yes or No to show which aspects are affected)											
Pedestrians aff	ected?	Yes	No	Property access affected	?	Yes	No	Traffic lanes affe	ected?	Yes	No
Cyclists affecte	ed?	Yes	No	Restricted parking affect	ed?	Yes	No	Delays or queuir	ng likely?	Yes	No
TSL/ Diagram (see TSL decision matrix for guidance)	terms o	al of To f Section Speed	emporary on 6 of La Limits 20	Is as required Speed Limits (TSL) are in and Transport Rule: Setting 017, Rule 54001/2017 Ingth and location)	(F	Times from and t	0)	Dates (Start and finish)	(Layou	am ref. t drawir TMDs)	
Attended day/ night	travellii betwee (House If a TS. tempor length 01N-02 Add ac require Note: V location records equiva same ii For leg	ouse no./RP) on (street or road name) a TSL is appropriate, add the TSL details - mporary speed (eg 70km/h), approximate ngth (eg 200m) and the location (eg RP IN-0260/0.50 or 23-53 Chews Lane). dd additional rows into this section if			house active place. Note house rest. RCA	ude the rs that the vity will ta e. : Activity rs may be ricted by A or contruments.	ike e the	Add the date or date range for this activity.	are atta TMP (e drawin) • the app manag diagrar TTM ha	a specification of the comment of th	ic g(s) that o the out or de traffic on the ok, if a level road A has
Unattended day/ night	k	m/h is ng ove n no./R	hereby f or the len (House)	n speed limit of Fixed for motor vehicles gth of m situated e no./RP) and (street or road name)	As a	above		As above	As above		
TSL duration	If yes, a	Vill the TSL be required for longer than 12 months? yes, attach the completed checklist from section I-18: Guidance on TMP Monitoring rocesses for TSLs to this TMP.						Yes No Delete either Yes or No to indicate whether the TSL will be required for longer than 12 months. If yes, attach the completed checklist from section I-18			

Contingency plan		
If long queues form or delays exceed 5mins (or any other period required by RCA), site to be disestablished or additional lanes made available.	Adjust TMD to suit unforeseen circumstances (eg weather or site overlaps with another work site).	Emergency services will be accommodated and access provided through the site as required.

Add additional contingencies:

Listed above are some common contingencies for worksites. Strike out any contingencies that are not applicable to the worksite.

Record additional contingencies for the worksite in this field.

Contact details											
	Name			24/7 contact number	CoPTTM ID	Qualification	Expiry date				
Principal	Organisation named on permit			24/7 contact number	Optional	Optional	Optional				
тмс	Name	Name				Optional	Optional				
Engineers' representative	Detail optional - Independent per employed by engineer whose re include TTM	24/7 contact number	Optional	Optional	Optional						
Contractor	State name of the contracting of the name of their contact person	24/7 contact number	Optional	Optional	Optional						
STMS	Name			24/7 contact number	CoPTTM ID number	Level of qualification	Date of expiry				
тс	Name	Name			CoPTTM ID number	Level of qualification	Date of expiry				
Others as required	Name			24/7 contact number	Optional	Optional	Optional				
	approval if STMS delegated authori does not apply (either prepared or app	•	e TM	IPs)							
Prepared / Approved	Name of the STMS who prepared/approved the TMP. If STMS has been delegated authority to approve TMPs, it may not need to be submitted to the RCA.	Date actioned	ST	MS signature	CoPTTM ID number	Level of qualification	Date of expiry				
	Name	Date		Signature	ID no.	Qualification	Expiry date				
This TMP meets Col	PTTM requirements		Nu	mber of diagra	ıms attached						
TMP returned for correction		Date actioned	Sig	nature	CoPTTM ID number	Level of qualification	Date of expiry				
	Name	Date		Signature	ID no.	Qualification	Expiry date				

Engineer/TMC to complete following section when approval or acceptance required										
Approved by TMC or engineer (delete one)		Date actioned	Signature	CoPTTM ID number	Level of qualification	Date of expiry				
	Name	Date	Signature	ID no.	Qualification	Expiry date				
Acceptance by TMC (only required if TMP approved by engineer)		Date actioned	Signature	CoPTTM ID number	Level of qualification	Date of expiry				
	Name	Date	Signature	ID no.	Qualification	Expiry date				

Qualifier for engineer or TMC approval

 $Approval \ of \ this \ TMP \ authorises \ the \ use \ of \ any \ regulatory \ signs \ included \ in \ the \ TMP \ or \ attached \ traffic \ management \ diagrams.$

This TMP is approved on the following basis:

- 1. To the best of the approving engineer's/TMC's judgment this TMP conforms to the requirements of CoPTTM.
- 2. This plan is approved on the basis that the activity, the location and the road environment have been correctly represented by the applicant. Any inaccuracy in the portrayal of this information is the responsibility of the applicant.
- 3. The TMP provides so far as is reasonably practicable, a safe and fit for purpose TTM system.
- 4. The STMS for the activity is reminded that it is the STMS's duty to postpone, cancel or modify operations due to the adverse traffic, weather or other conditions that affect the safety of this site.

E1.4 Example of TMP - full form

RCA consent (eg RCA contract refe	CAR/WAP) and/or erence							
TRAFFIC MAN	AGEMENT PLAN	I (TMP) – FULL	FORM					
Use this form for co temporary traffic m	omplex activities. Refe anagement (CoPTTM	er to the NZ Transpo l), section E, appen	ort Agency's Traffi dix A for a guide o	c control devices manual, pa n how to complete each field	rt 8 Code of prac	ctice for		
Organisations	TMP reference:	Contractor (Wor	king space):	Principal (Client):				
/TMP reference		Contractor (TTN	1):	RCA:				
	Road	d names and subu	rb	House no./RPs (from and to)	Road level	Permanent speed		
Location details and road characteristics								
Traffic details (main route)	AADT			Peak flows				
Description of wo	rk activity							
Planned work pro	_				-	1		
Consider significa stages, for example road closures detours no activity periods.	ant	Time	En	d date	Time			

Alternative dates if activity delayed

Road aspects affected	l (delete	e either	Yes or No to show which aspects	are affec	cted)			
Pedestrians affected?	Yes	No	Property access affected?	Yes	No	Traffic lanes affected?	Yes	No
Cyclists affected?	Yes	No	Restricted parking affected?	Yes	No	Delays or queuing likely?	Yes	No
Proposed traffic mana	gemen	t metho	ods					
Installation (includes parking of plant and materials storage)								
Attended (day)								
Attended (night)								
Unattended (day)								
Unattended (night)								
Detour route	If Yes,	has con	ute go into another RCA's roading ne firmation of acceptance been reques	ted from th	nat RCA?		s or No)	
Removal	Note:	Confirma	ation of acceptance from affected RC.	A must be	submitte	d prior to occupying the site.		

Section E - Page 10

Proposed TSL	Proposed TSLs (see TSL decision matrix for guidance)								
	Approval of Temporary Speed Limits (TSL) are in terms of Section 6 of Land Transport Rule: Setting of Speed Limits 2017, Rule 54001/2017 (List speed, length and location)	Times (From and to)	Dates (Start and finish)	Diagram ref. no.s (Layout drawings or traffic management diagrams)					
Attended day/night	A temporary maximum speed limit of km/h is hereby fixed for motor vehicles travelling over the length of m situated between (House no./RP) and (House no./RP) on (street or road name)								
Unattended day/night	A temporary maximum speed limit of km/h is hereby fixed for motor vehicles travelling over the length of m situated between (House no./RP) and (House no./RP) on (street or road name)								
TSL duration	Will the TSL be required for longer than 12 months? If yes, attach the completed checklist from section I-18: G for TSLs to this TMP.	Guidance on TMP M	Monitoring Processes	Yes No					

Positive traffic management measures

_	4				
1.0	ntin	MAR	1011	n	anc
CU	ntin	uci	ILV	v	ans

Generic contingencies for:

- major incidents
- incidents
- pre planed detours.

Remove any options which do not apply to your job

Major Incident

A major incident is described as:

- Fatality or notifiable injury real or potential
- Significant property damage, or
- Emergency services (police, fire, etc) require access or control of the site.

Actions

The STMS must immediately conduct the following:

- stop all activity and traffic movement
- secure the site to prevent (further) injury or damage
- contact the appropriate emergency authorities
- render first aid if competent and able to do so
- notify the RCA representative and / or the engineer
- under the guidance of the officer in charge of the site, reduce effects of TTM on the road or remove the activity if safe to do so
- re-establish TTM and traffic movements when advised by emergency authorities that it is safe to do so
- · Comply with any obligation to notify WorkSafe.

Incident

An incident is described as:

- excessive delays real or potential
- minor or non-inquiry accident that has the potential to affect traffic flow
- structural failure of the road.

Actions

The STMS must immediately conduct the following:

- stop all activity and traffic movement if required
- secure the site to prevent the prospect of injury or further damage
- notify the RCA representative and / or the engineer
- STMS to implement a plan to safely remove TTM and to establish normal traffic flow if safe to do so
- re-establish TTM and traffic movements when it is safe to do so and when traffic volumes have reduced.

Detour

If because of the on-site activity it will not be possible to remove or reduce the effects of TTM once it is established a detour route must be designed. This is likely for:

- excessive delays when using an alternating flow design for TTM
- redirecting one direction of flow and / or
- total road closure and redirection of traffic until such time that traffic volumes reduce and tailbacks have been cleared.

The risks in the type of work being undertaken, the risks inherent in the detour, the probable duration of closure and availability and suitability of detour routes need to be considered.

The detour and route must be designed including:

- pre- approval form the RCA's whose roads will be used or affected by the detour route
- ensure that TTM equipment for the detour signs etc are on site and pre-installed.

Actions

When it is necessary to implement the pre-planned detour the STMS must immediately undertake the following:

- Notify the RCA and / or the engineer when the detour is to be established
- Drive through the detour in both directions to check that it is stable and safe
- Remove the detour as soon as it practicable and safe to do so and the traffic volumes have reduced and tailbacks have cleared
- Notify the RCA and / or the engineer when the detour has been disestablished and normal traffic flows have resumed.

Note also the requirements for no interference at an accident scene:

In the event of an accident involving serious harm the STMS must ensure that nothing, including TTM equipment, is removed or disturbed and any wreckage article or thing must not be disturbed or interfered with, except to:

- save a life of, prevent harm to or relieve the suffering of any person, or
- make the site safe or to minimise the risk of a further accident; or
- maintain the access of the general public to an essential service or utility, or
- · prevent serious damage to or serious loss of property, or
- follow the direction of a constable acting in his or her duties or act with the permission of an inspector.

Other contingencies to be identified by the applicant (i.e. steel plates to

(i.e. steel plates to quickly cover excavations)

Parking restriction(s) alteration authority	Will controlled street parking	g be affected?	Yes No	Has approval been granted?	Yes No
Authorisation to work at permanent	Will portable traffic signals be permanent traffic signals be		Yes No	Has approval been granted?	Yes No
traffic signal sites					·
Road closure authorisation(s)	Will full carriageway closure more than 5 minutes (or oth time)?		Yes No	Has approval been granted?	Yes No
. ,					
Bus stop relocation(s) -	Will bus stop(s) be obstructe	ed by the activity?	Yes No	Has approval been granted?	Yes No
closure(s)					
Authorisation to use portable traffic	Make, model and description/number				
signals	NZTA compliant?	Yes No (de	lete either Ye	es or No)	
EED					
	Yes No				
ls an EED applicable?	(delete either Yes or No)	EED attached?	Yes		
		EED attached?			-
	(delete either Yes or No)	EED attached?			
	(delete either Yes or No)	EED attached?			
	(delete either Yes or No)	EED attached?			
	(delete either Yes or No)	EED attached?			
Delay calculations/tria	(delete either Yes or No)	EED attached?			
	(delete either Yes or No)	EED attached?			
Delay calculations/tria	(delete either Yes or No)	EED attached?			
Delay calculations/tria	(delete either Yes or No)	EED attached?			
Delay calculations/tria	(delete either Yes or No)	EED attached?			
Delay calculations/tria	(delete either Yes or No)	EED attached?			

On-site monitoring plan	1				
Attended (day and/or night)					
Unattended (day and/or night)					
Method for recording d	aily site TTM activity (eg CoPTTM on-site record)				
Site safety measures					
Other information					
Site specific layout diag	grams				
Number	Title				
Contact details		24/7 contact	CoPTTM		Evenime
	Name	number	ID	Qualification	Expiry date
Principal					
TMC					
Engineers' representative					
Contractor					
STMS					
тс					
Others as required					

TMP preparation						
Preparation						
.,	Name (STMS qualified)	Date	Signature	ID no.	Qualification	Expiry date
This TMP meets CoP	PTTM requirements		Number of	diagrams atta	iched	
TMP returned for					·	
correction (if required)	Name	Date	Signature	ID no.	Qualification	Expiry date
Engineer/TMC to cor	mplete following section when approve	al or accepta	nce required			
Approved by TMC/engineer						
(delete one)	Name	Date	Signature	ID no.	Qualification	Expiry date
Acceptance by TMC (only required						
if TMP approved by engineer)	Name	Date	Signature	ID no.	Qualification	Expiry date
Qualifier for enginee	r or TMC approval					
Annual of this TMD				l t		

Approval of this TMP authorises the use of any regulatory signs included in the TMP or attached traffic management diagrams.

This TMP is approved on the following basis:

- 1. To the best of the approving engineer's/TMC's judgment this TMP conforms to the requirements of CoPTTM.
- 2. This plan is approved on the basis that the activity, the location and the road environment have been correctly represented by the applicant. Any inaccuracy in the portrayal of this information is the responsibility of the applicant.
- 3. The TMP provides so far as is reasonably practicable, a safe and fit for purpose TTM system.
- 4. The STMS for the activity is reminded that it is the STMS's duty to postpone, cancel or modify operations due to the adverse traffic, weather or other conditions that affect the safety of this site.

Notification to TMC prior to occupying worksite/Notification completed						
Type of notification to TMC required		Notification completed	Date Time			

E1.5 Guidelines for completion of TMP - full form

RCA consent (eg CAR/WAP) and/or RCA contract reference

Add RCA consent reference, for example the corridor access request (CAR) or work access permit (WAP) and/or any RCA contract reference.

TRAFFIC MANAGEMENT PLAN (TMP) - FULL FORM

Use this form for complex activities. Refer to the NZ Transport Agency's Traffic control devices manual, part 8 Code of practice for temporary traffic management (CoPTTM), section E, appendix A for a guide on how to complete each field.

Organisations /TMP	TMP reference: Add the RCA's and contractor's reference number	Contractor (Working space): State the name of the contractor responsible for the working space	Principal (Client): State the name of the principal or client for this project (eg NZTA or Chorus)			
reference		Contractor (TTM): State the name of the contractor responsible for the TTM	RCA: State the name of the RCA who controls the road that the worksite will be on. Note: There can be more than one RCA.			
	Road	names and suburb	House no./RPs (from and to)	Road level	Permanent speed	
Location details and road characteristics	Include the road nan intersections. Also in	ne/s and any affected oclude the suburb	Enter house numbers, route positions or power pole numbers where applicable	Enter RCA designation	Enter highest permanent limit	
	As above		As above	As above	As above	
	AADT		Peak flows	•		
Traffic details (main route) Include AADT where available. The RCA or engineer must provide this information available.			Include peak hour and he available. The RCA or engineer muif available.	•		

Description of work activity

Briefly provide an accurate and complete description of the work or activity eg repairs to median barrier

Planned work programme								
Start date	Enter earliest date activity may start	Time	Enter earliest time activity may start	End date	Enter latest date activity may finish allowing for unforeseen issues	Time	Enter latest time activity may finish allowing for unforeseen issues	
Consider significant stages, for example:	Provide details of any si	gnificar	nt stages					
Alternative dates if activity delayed	For larger activities, idea	ntify any	y alternative	dates that ca	an be scheduled if the w	vork is de	layed	

Road aspects affected	(delete	either Ye	es or No to show which aspects an	e affected	d)			
Pedestrians affected?	Yes	No	Property access affected?	Yes	No	Traffic lanes affected?	Yes	No
Cyclists affected?	Yes	No	Restricted parking affected?	Yes	No	Delays or queuing likely?	Yes	No
Use the 'Aspects affec layout drawings/TMDs			ntify how the activity will affect to TMP	he road.	These	effects will need to be cove	ered in t	he
Proposed traffic manag	gement	method	s					
Installation (includes parking of plant and materials storage)	Provid	de full de	escription of all installation proc	edures f	or oper	ations that involve TTM		
Attended (day)			escription of all procedures for ore the activity is underway	pperatior	ıs that i	involve TTM or impact upon	TTM fo	ır
Attended (night)	opera	tion whe	escription of all procedures for or ere the activity is underway s of night overhead lighting	peratior	ns that i	involve TTM or impact upon	TTM fo	nr
Unattended (day)	opera	tion whe	escription of all procedures for or ere the activity is incomplete bu troad users					
Unattended (night)	opera	tion whe	escription of all procedures for or ere the activity is incomplete bu et road users	,		, ,		
	Includ	le details	s of the route of the detour (pro	vide a m	ap if de	etour is complex)		
Detour route	If Yes, Note: 0 If the accep	has confir Confirmati detour ti tance fr	e go into another RCA's roading netw mation of acceptance been requested on of acceptance from affected RCA r ransfers road users to another to om that RCA. The confirmation ying the site.	from that nust be su RCA's ro	RCA? bmitted p ading r	orior to occupying the site. network, request confirmation	on of	tted
Removal	Provid	le full de	escription of all removal proced	ures for (operatio	ons that involve TTM		

Section E - Page 17

Proposed TSLs	Proposed TSLs (see TSL decision matrix for guidance)									
	TSL details as required Approval of Temporary Speed Limits (TSL) are in terms of Section 6 of Land Transport Rule: Setting of Speed Limits 2017, Rule 54001/2017 (List speed, length and location)	Times (From and to)	Dates (Start and finish)	Diagram ref. no.s (Layout drawings or traffic management diagrams)						
Attended day/night	A temporary maximum speed limit of km/h is hereby fixed for motor vehicles travelling over the length of m situated between (House no./RP) and (House no./RP) on (street or road name) If a TSL is appropriate, add the TSL details - temporary speed (eg 70km/h), approximate length (eg 200m) and the location (eg RP 01N-0260/0.50 or 23-53 Chews Lane). Add additional rows into this section if required. Note: When the worksite is set up, the actual location of the TSL signs will need to be recorded on the on-site record or the equivalent company sheet that records the same information. For legal purposes (eg speed enforcement), this information must be retained for 12 months and be provided on request.	Include the hours that the activity will take place Note: Activity hours may be restricted by the RCA or contract documents.	Add the date or date range for this activity	List the reference for either: • the site specific layout drawing(s) that are attached to the TMP (eg layout drawing 1, 2), or • the appropriate traffic management diagram(s) from the TTM handbook, if worksite is on a level LV or level 1 road where the RCA has approved the use of generic TMDs.						
Unattended day/night	A temporary maximum speed limit of km/h is hereby fixed for motor vehicles travelling over the length of m situated between (House no./RP) and (House no./RP) on (street or road name) As above	As above	As above	As above						
TSL duration	Will the TSL be required for longer than 12 months? If yes, attach the completed checklist from section I-18: for TSLs to this TMP.	Guidance on TMI	P Monitoring Processes	Yes No Delete either Yes or No to indicate whether the TSL will be required for longer than 12 months. If yes, attach the completed checklist from section I-18						

Positive traffic management measures

Refer to section C10.1.1

Positive traffic management measures must be used when installing TSLs of:

- less than 70km/h in areas with permanent posted speed limits of 100km/h, or
- less than 50km/h in areas with a permanent posted speed limit of 70 or 80km/h.

Detail the extent of positive traffic management to be undertaken when:

- temporary speed restrictions below 70km/h in areas with existing permanent speed limits of 100km/h, or below 50km/h in areas with existing permanent speed limits of 70km/h or 80km/h, or less than 30km/h in a 50km/h area
- traffic is stopped to allow work to proceed
- traffic is reduced to one lane.

Contingency plans

Generic contingencies for:

- major incidents
- incidents
- pre planed detours.

Remove any options which do not apply to your job

Record the contingencies for the worksite. Consider the items listed and add or amend as required. Also add additional contingencies appropriate to the worksite

Major Incident

A major incident is described as:

- Fatality or notifiable injury real or potential
- Significant property damage, or
- Emergency services (police, fire, etc) require access or control of the site.

Actions

The STMS must immediately conduct the following:

- stop all activity and traffic movement
- secure the site to prevent (further) injury or damage
- contact the appropriate emergency authorities
- render first aid if competent and able to do so
- notify the RCA representative and / or the engineer
- under the guidance of the officer in charge of the site, reduce effects of TTM on the road or remove the activity if safe to do so
- re-establish TTM and traffic movements when advised by emergency authorities that it is safe to do so
- Comply with any obligation to notify WorkSafe.

Incident

An incident is described as:

- excessive delays real or potential
- minor or non-inquiry accident that has the potential to affect traffic flow
- structural failure of the road.

Actions

The STMS must immediately conduct the following:

- stop all activity and traffic movement if required
- secure the site to prevent the prospect of injury or further damage
- notify the RCA representative and / or the engineer
- STMS to implement a plan to safely remove TTM and to establish normal traffic flow if safe to do so
- re-establish TTM and traffic movements when it is safe to do so and when traffic volumes have reduced.

Detour

If because of the on-site activity it will not be possible to remove or reduce the effects of TTM once it is established a detour route must be designed. This is likely for:

- excessive delays when using an alternating flow design for TTM
- redirecting one direction of flow and / or
- total road closure and redirection of traffic until such time that traffic volumes reduce and tailbacks have been cleared

The risks in the type of work being undertaken, the risks inherent in the detour, the probable duration of closure and availability and suitability of detour routes need to be considered.

The detour and route must be designed including:

- pre- approval form the RCA's whose roads will be used or affected by the detour route
- ensure that TTM equipment for the detour signs etc are on site an pre-installed.

Actions

When it is necessary to implement the pre-planned detour the STMS must immediately undertake the following:

- Notify the RCA and / or the engineer when the detour is to be established
- Drive through the detour in both directions to check that it is stable and safe
- Remove the detour as soon as it practicable and safe to do so and the traffic volumes have reduced and tailbacks have cleared
- Notify the RCA and / or the engineer when the detour has been disestablished and normal traffic flows have resumed.

Note also the requirements for no interference at an accident scene:

In the event of an accident involving serious harm the STMS must ensure that nothing, including TTM equipment, is removed or disturbed and any wreckage article or thing must not be disturbed or interfered with, except to:

- save a life of, prevent harm to or relieve the suffering of any person, or
- make the site safe or to minimise the risk of a further accident; or
- maintain the access of the general public to an essential service or utility, or
- prevent serious damage to or serious loss of property, or
- follow the direction of a constable acting in his or her duties or act with the permission of an inspector.

Other contingencies to be identified by the applicant

(i.e. steel plates to quickly cover excavations)

Add additional contingencies appropriate to the worksite

Authorisations									
Parking	Will controlled street parking be affected?	parking be affected? Yes No Has approval been granted?							
restriction(s) alteration authority	If no approval has been granted, make app	olication							
Authorisation to work at permanent	Will portable traffic signals be used or permanent traffic signals be changed?								
traffic signal sites	If no approval has been granted, make app	olication							
Road closure	Will full carriageway closure continue for more than 5 minutes (or other RCA stipulated time)?	Yes No	Has approval been granted?	Yes No					
authorisation(s)	If no approval has been granted, make app	olication							
Bus stop	Will bus stop(s) be obstructed by the activity?	Yes No	Has approval been granted?	Yes No					
relocation(s) – closure(s)	Required where a bus stop/s is obstructed application	by activity	. If no approval has been granted, make						

Authorisation to use portable traffic	Make, model and description/number	Include make, model and description number of the portable traffic sig					
signals	NZTA compliant?	Yes No (delete either Yes or No) Confirm that the signals are approved for use by the NZTA.					
EED							
Is an EED applicable?	Yes No (delete either Yes or No) Indicate if an EED has been agreed for this worksite	EED attached?	Yes If yes then attach the EED to the TMP				

Delay calculations/trial plan to determine potential extent of delays

Required where potential delays may occur. RCA will define when these are required once draft plan is submitted.

Public notification plan

Required where activity may cause disruption to community. RCA to define when these are required Include details of notices proposed to be advertised via local radio or newspapers or distributed to local residents. Refer contract documentation and RCA requirements

Public notification plan	attached?	Yes No (delete either Yes or No)							
On-site monitoring plan									
Attended (day and/or night)	Detail the m holiday brea For example may be: 2 hourly f Daily for c	frequency of monitoring the continued effectiveness of the traffic management measures conitoring of attended and unattended worksites both overnight and during weekends or asks at an attended static worksite with the STMS or TC on-site, the inspection frequency for signs, portable channelling and delineation devices and arrow boards leanliness of safety garments, non-portable equipment and flashing beacons on vehicles asly for wearing of safety jackets.							
Unattended (day and/or night)	This field must be completed for any unattended sites On unattended worksites (overnight, weekends etc.) the STMS assesses the needs of that site and includes details of monitoring in the TMP								

Section E - Page 21

Method for recording daily site TTM activity (eg CoPTTM on-site record)

State how on-site TTM activity will be recorded.

This could be the CoPTTM on-site record or the equivalent company document provided it covers the following information:

- details of the STMS who is in charge of the worksite (name, qualification, ID and expiry date of qualification)
- If worksite delegated to a TC (level 1) or STMS-NP (only on limited level 2 worksites), details of the TC/STMS-NP who is in charge of the worksite (name, qualification, ID and expiry date of qualification)
- the worksite monitoring including:
 - site set-up
 - 2-hourly monitoring
 - site removal
- details of any TSLs installed:
 - date installed
 - time installed
 - placement (RPs or street numbers)
 - length of TSL (in metres)
 - date removed
 - time removed.

If using a company on-site record instead of the CoPTTM on-site record, you must attach that document to the TMP.

Site safety measures

In this section include special items such as overhead lighting for night time MTC

Other information

Further details may be required as a result of specific site conditions or contractual requirements. In addition, TMPs should also include the following as appropriate:

- liaison with emergency services and public transport operators (if they could be affected by the worksite)
- changes to parking controls
- traffic environment details of speed limit, parking, traffic signals, pedestrian crossings, road alignment and hierarchy
- specialised equipment such as pilot vehicles, use of temporary traffic signals
- materials storage
- pedestrian barriers and equipment to be used
- queuing
- plant operational requirements, eg truck waiting and filling areas.

TMPs for mobile operations should also include the following additional information:

- the type and function of each vehicle in the mobile operation
- the vehicles that will be equipped with attenuators and arrow boards and their location within the worksite
- the number, location and, duration of exposure and tasks of personnel who are permitted to leave their vehicles
- the method of inter-vehicle communication.

Site specific layout dia	grams											
Number	Title											
Enter applicant diagram number. Also consider whether a layout diagram is required for set-up /removal of the worksite.	Enter name of attached diagram											
As above	As above											
As above	As above	As above										
As above	As above											
Contact details												
	Name	24/7 contact number	CoPTTM ID	Qualification	Expiry date							
Principal	Organisation named on permit	24/7 contact number	Optional	Optional	Optional							
ТМС	Name	24/7 contact number	Optional	Optional	Optional							
Engineers' representative	Detail optional - Independent person employed by engineer whose responsibilities include TTM	24/7 contact number	Optional	Optional	Optional							
Contractor	State name of the contracting company and the name of their contact person	24/7 contact number	Optional	Optional	Optional							
STMS	Name Where multiple names are included in the TMP, the name of the STMS in charge must be written on the On-site record	24/7 contact number	CoPTTM ID number	Level of qualification	Date of expiry							
тс	Name	24/7 contact number	CoPTTM ID number	Level of qualification	Date of expiry							
Others as required	Name	24/7 contact number	Optional	Optional	Optional							

TMP preparation										
Preparation	STMS signature	Date prepared	STMS signature	CoPTTM ID number	Level of qualification	Expiry date				
	Name (STMS qualified)	Date	Signature	ID no.	Qualification	Expiry date				
This TMP meets CoPTTM requirements Number of diagrams attached										
TMP returned for correction	Name of TMC or engineer returning TMP	Date accepted	Signature	CoPTTM ID number	Level of qualification	Expiry date				
(if required)	Name	Date	Signature	ID no.	Qualification	Expiry date				
Engineer/TMC to con	nplete following section when approva	l or acceptan	ce required							
Approved by TMC/engineer	Name of TMC or engineer approving TMP	Date accepted	Signature	CoPTTM ID number	Level of qualification	Expiry date				
(delete one)	Name	Date	Signature	ID no.	Qualification	Expiry date				
Acceptance by TMC (only required if TMP approved by engineer)	Name of TMC	Date accepted	Signature	CoPTTM ID number	Level of qualification	Expiry date				
	Name	Date	Signature	ID no.	Qualification	Expiry date				

Qualifier for engineer or TMC approval

Approval of this TMP authorises the use of any regulatory signs included in the TMP or attached traffic management diagrams.

This TMP is approved on the following basis:

- 1. To the best of the approving engineer's/TMC's judgment this TMP conforms to the requirements of CoPTTM.
- 2. This plan is approved on the basis that the activity, the location and the road environment have been correctly represented by the applicant. Any inaccuracy in the portrayal of this information is the responsibility of the applicant.
- 3. The TMP provides so far as is reasonably practicable, a safe and fit for purpose TTM system.
- 4. The STMS for the activity is reminded that it is the STMS's duty to postpone, cancel or modify operations due to the adverse traffic, weather or other conditions that affect the safety of this site.

Notification to TMC prior to occupying worksite/Notification completed									
Type of notification to TMC required	,	Notification completed	112114	Record date notification was completed					
			Time	Record time notification was completed					

E1.6 Example of on-site record

TMP or generi	c plan reference						
ON-SITE RE	CORD must be retained with TMP for 12 mo	onths.			Today's date		
Location details	Road names(s):	House number/RPs	House number/RPs:				
Working sp	ace						
Person responsible for working							
space	Name	1' TTM (Signature	11. (1		t t t	
Where the STI	MS/TC is responsible for both the wor	rking space and TTM they s	sign above an	d in the	appropriate I I M	box below	
TTM							
STMS in charge of TTM							
	Name	TTM ID Number	Warrant expir	y date	Signature		Time
Worksite handover accepted by							
replacement	Name	ID Number	Warrant expir	y date 3	Signature	Time	
STMS	Tick to confirm handover briefing completed						
Delegation							
Worksite control							
accepted by TC/STMS-NP	Name	ID Number	Warrant expir	y date	Signature		Time
10/01/10/11	Tick to confirm briefing completed						
Temporary	speed limit						
Street/road na	ame (RPs or street numbers):	TSL action	Date:	Time:	TSL speed	Length of	TSL (m):
		TSL installed					
	Tai	TSL remains in place					
From:	To:	TSL removed				1	
Street/road na	ame (RPs or street numbers):	TSL action	Date:	Time:	ISL speed	Length of	ISL (m):
		TSL installed TSL remains in place					
From:	To:	TSL removed					
	ame (RPs or street numbers):	TSL action	Date:	Time:	TSI sneed	Length of	TSI (m)
Street/road III	and the or or or or or.	TSL installed	Dutoi	Time.	TOL Speed	Longino	. 02 (111).
		TSL remains in place					
From:	То:	TSL removed					
	-						

Worksite monitoring TTM to be monitored and 2 hourly inspections documented below. TTM 2 hourly 2 hourly 2 hourly 2 hourly 2 hourly TTM Items to be inspected check check check check check set-up removal High-visibility garment worn by all? Signs positioned as per TMP? Conflicting signs covered? Correct delineation as per TMP? Lane widths appropriate? Appropriate positive TTM used? Footpath standards met? Cycle lane standards met? Traffic flows OK? Adequate property access? Add others as required Time inspection completed: Signature: Comments: Time Adjustment made and reason for change

E1.7 Engineering exception decision

ENGINEERING EXCEPTION DECISION									
Name of RC	A	EED No							
Basic descri the activity as with EED									
Location det	Location detail and scheduled dates								
	This EED re	elates to	TTM activities at:			From:	From:		
Location					Dates:	To:			
It is proposed	I to vary the	require	ments of CoPTTM.						
WHAT the proposed act		(a) desci	ribe the road environme	nt constr	aint, (b) s	tate Col	PTTM require	ements for the	
a. The road of constraint		nt							
b.CoPTTM re the propos	equirement sed activity								
WHY CoPTT	M complia	nt TTM s	should not/cannot be i	nstalled	.				
HOW will sat	fety be ens	ured?							
This EED mu Agency.	ust be attac	hed to	the TMP. Any generic l	EEDs m	ust be fo	rwarded	d to the NZ T	ransport	
EED – Propo	sal								
Signed for	_								
and behalf o	f: Insert co	ontractor	's name	ı					
Signed by:	Name				esignation		ID number	Expiry date	
	Olava a tu					5.	-4-		
EED – Appro	Signatu	re				Da	ate		
Signed for	vea by								
and behalf o	f: Insert R	CA name							
Signed by:	Name			De	esignation		ID number	Expiry date	
olgiled by.									
	Signatu	re				Da	ate		

E1.8 Example of checking process for generic traffic management plans (TMPs)

Checking proces	ss for generic TMPs							
This form, or a sir	nilar company record, must be c	completed pri	ior to set i	ıp of a	a worksite where a	generic TM	IP is used.	
Location details								
Road name(s)	ame(s)			(s)			Suburb	
			House number/RP(s)					
Generic TMP TMD no(s).			Note: The checking princlude all the TMDs to					
Category	Points to consider		Υ	N	Comment/Mitiga	tion		
Road level	Is this at the correct road lev	rel?						
	Are the following catered for TMP?	in the gener	ric					
Shape	 Intersections 							
·	Vertical Curves (hills) Horizontal Curves (corne Sufficient advance warning)	•						
	Check that there is:							
Direction and protection	sufficient length to place direction and protection	the planned						
	 sufficient road width to pl planned direction and pro minimum lane width is 2. 	otection ie						
	adequate sight distance of the stance o	on both sides	s					
	sufficient room to accoming required positive traffic controls.							
Proposed speed	Is a TSL required?							
restrictions	Refer to the TSL decision m CoPTTM (section E Append							
Plant and equipment	Will your plant and equipmed designated working space?	nt fit within th	he					
Personal safety	Are all workers able to carry within the designated working		ork					
r ersonar surety	If not are they covered by th inspections?	e rules for						
	Is diagram(s) detailed in the	generic TMI	P?					
Layout diagrams	section of the TMP?							
RCA notification	Has the RCA been notified?							
Completed by:								
STMS/TC in charge of worksite								
	Name		Sign	ature		Date	Qualification	ID number
(All names to be entered before								
site set-up)	Name		Signature			Date	Qualification	ID number

E1.9 Additional information about completion of traffic management plans (TMPs)

E1.9.1 Generic TMPs

Generic TMPs should, in addition to the above requirements:

- allow for an annual review by the RCA
- be readily changeable at any time over the term to allow for worksite and personnel changes
- allow for the conditions under which the RCA may be prepared to delegate authority to fix temporary speed limits.

E1.9.2 Mobile operation TMPs

TMPs for mobile operations should also include the following additional information:

- the type and function of each vehicle in the mobile team
- the vehicles that will be equipped with attenuators and arrow boards, and their location within the closure
- the number, location and duration of exposure, and tasks of personnel who are permitted to leave their vehicles
- the method of inter-vehicle communication.

E1.9.3 Additional information

In addition, TMPs should also include the following as appropriate:

- liaison with emergency services and public transport operators (if they could be affected by the worksite)
- changes to parking controls
- traffic environment details of speed limit, parking, traffic signals, pedestrian crossings, road alignment and hierarchy
- specialised equipment such as pilot vehicles, use of portable traffic signals
- materials storage
- pedestrian safety fences and delineation and equipment to be used
- aueuing
- plant operational requirements, eg truck waiting and filling areas.

E1.10 Example of schedule of specific job requirements for traffic management and safety

management and safety

SCHEDULE OF SPECIFIC JOB REQUIREMENTS FOR TRAFFIC MANAGEMENT AND SAFETY

To be included in contract documents.

Contract number

Contract name

Operational requirements

1. Level of temporary traffic management

The temporary traffic management must be to: (delete those that do not apply)

- Level LV
- Level 1
- Level 2
- Level 3

2. Hours of work

The contractor must programme work to ensure that contract activities affecting traffic flow are not carried out on-site between the hours specified below, Monday to Friday inclusive.

No work other than emergency or maintenance work must be undertaken on weekends without prior approval of the engineer. Hours/days when work is prohibited or restricted.

3. Project specific conditions

4. Excessive traffic delays

The steps outlined in the traffic management plan to deal with excessive traffic delays must be implemented once the traffic delay exceeds minutes. The contractor is responsible for monitoring of traffic delay.

5. Advice to other parties

Public notification is not required/is required. If required, the details are:

Parties with access affected

6. Temporary traffic management

Temporary traffic management must conform to the CoPTTM.

7. Condition of road surface


Deduction made for temporary road not being sealed and maintained for greater than days at \$ calendar day

8. Basis of payment

Payment must be in accordance with:

- lump sum
 - \$
- daily rate \$ per 24 hoursprovisional sum \$ per 24 hours
- 9. Positive traffic management specific requirements

E2 Appendix B: Temporary speed limit (TSL) decision matrix worksheet



E3 Appendix C: Procedures for safety audit/review of worksites


E3.1 Introduction

E3.1.1 Focus for auditor/reviewer

The initial focus for the auditor/reviewer is the worksite.

The auditor/reviewer also assesses:

- the design of the TMP
- application of CoPTTM and Local authority standards.



E3.1.2 Audit principles

Key principles that underpin all audits/reviews are:

- auditors/reviewers are consistent in their approach
- audits/reviews are fair
- where required, auditors/reviewers reference the relevant standard (either CoPTTM or local authority standards) when explaining issues
- auditors/reviewers take time to educate and encourage high standard/acceptable TTM work activities.

E3.1.3 Audit/review resources

Audit/review forms are available from the CoPTTM pages of the NZTA website (refer to Forms used for traffic management).

Audit/review resources are also available in section I: 21 Audit/review resources of the CoPTTM pages of the NZTA website.

E3.2 TTM safety audit/review methodology

E3.2.1 General methodology

An audit/review includes the following:

- a review of the worksite
- completion of the site condition rating (SCR) form
- a review of the TMP and onsite record (where required).

The general methodology recommended for using these procedures is:

proceed through the worksite (including intersecting roads) making note
of issues and recording them on the SCR form. Photographs or videos
are recommended to record items of interest

If at any stage the auditor/reviewer considers the worksite to be of high risk to road users/workers, immediate corrective action must be initiated

review the on-site documentation (TMP and on-site record) as required.
 Refer to appendix C, subsection E3.4 Sighting TMPs rework the SCR to reflect any approved variances to the CoPTTM and local authority standards

Note: Where there are issues with the design and/or approval of the TMP, these are recorded on the SCR for follow-up

- establish the site condition rating:
 - for the full audit/review:
 - SCR is based on the total accumulated points for the worksite and other worksite aspects
 - for the short audit:
 - total the number of scores for each rating given against each standards category
- take appropriate actions with respect to SCR outcomes (refer appendix C, subsection E3.5 Actions following SCR).

A copy of the SCR is to be provided to the STMS and the company responsible for the TTM. A copy may also be provided to the company responsible for the working space and the principal if required.

E3.3 SCR for full and short audit/review

E3.3.1 Full audit/review - site condition rating

The SCR evaluates temporary traffic management (TTM) compliance with the minimum requirements of the CoPTTM and Local Authority standards.

Each element of non-compliance is given a value that reflects its importance in terms of TTM at the worksite and is tallied to give the SCR.

E3.3.1.1 SCR categories

High standard	Acceptable	Needs improvement
0 - 10	11 - 25	26 - 50

Unacceptable (Other)	Unacceptable	Unacceptable (multiple issues)
SCR under 51 and item(s) in OTHER WORKSITE ASPECTS are marked N	SCR 51+ and Item(s) in OTHER WORKSITE ASPECTS are marked Y	SCR 51+ and item(s) in OTHER WORKSITE ASPECTS are marked N

Dangerous
51+ and
LOW RISK? is rated No

A notice of non-conformance may be issued when the worksite is rated Unacceptable (Other), Unacceptable, Unacceptable (multiple issues) or Dangerous. Refer to appendix C, subsection E3.4 Sighting TMPs and subsection E3.6 Notice of non-conformance.

E3.3.2 Short audit - site condition rating

The SCR evaluates TTM compliance with the minimum requirements of the CoPTTM and Local Authority standards.

Short audit ratings are as follows:

- Acceptable
- Needs improvement
- Dangerous.

If an item is rated dangerous it must be rectified at once.

If there are one or more dangerous ratings the auditor/reviewer must consider issuing a notice of non-conformance.

In the case of issuing a notice of non-conformance, the auditor/reviewer must either provide a detailed report, and if possible photographs, or a SCR using the full audit/review.

E3.4 Sighting TMPs

E3.4.1 When to site onsite documentation

Reviewing the onsite documentation (TMP and on-site record) confirms that:

- there is an approved TMP for the worksite
- the worksite layout complies with the approved TMP (including any engineering exception decisions (EEDs) approved for the worksite)
- the TMP, which may include an EED, is appropriate to the actual situation
- any authorised TSLs are appropriate to the worksite and activity
- the on-site record has been completed and is correct.

Guidelines for when to review the onsite documentation are set out below:

For both attended and unattended worksites				
High standard (0 - 10)	Optional			
Acceptable (11 - 25)	Optional (unless worksite SCR is high risk)			
Needs improvement (26 - 50)	Optional (unless worksite SCR is high risk)			
Unacceptable	Must check documentation			
Dangerous	Must check documentation			

RCAs may establish their own policies for when onsite documentation is to be reviewed.

E3.5 Actions following SCR

E3.5.1 SCR of high standard or acceptable

The auditor/reviewer need not take any action on site when the SCR is either within the High Standard or Acceptable categories. It is recommended however, that the STMS be advised of these good audit/review results at the time of the audit/review.

E3.5.2 SCR of needs improvement

Where the SCR is Needs improvement, the STMS must be informed of the audit/review result immediately. The auditor/reviewer must discuss the TTM features that are non-complying with the STMS and make recommendations as to how the worksite safety can be improved.

The STMS must undertake remedial action as soon as possible and has a maximum of four hours to bring the SCR to an Acceptable standard or better.

E3.5.3 SCR of Unacceptable (Other)

Where the SCR is Unacceptable (Other) the STMS and/or organisation must be informed of the audit/review result immediately. The auditor/reviewer will advise the STMS/Contractor as to expected actions. This may include anything from the STMS implementing immediate remedial actions through to the ceasing of all activity/work and making the site safe until such time as the TTM is improved to Acceptable SCR or better.

A stop works order (SWO) may be issued in some circumstances such as where no approval exists for the activity/TMP.

E3.5.4 SCR of Unacceptable, Unacceptable (multiple issues) and Dangerous Where the SCR is Unacceptable, Unacceptable (multiple issues) or Dangerous the STMS and/or organisation must be informed of the audit/review result immediately.

A rating of Dangerous is grounds for the issuing of a SWO. In some circumstances, a rating of Unacceptable, or Unacceptable (multiple issues) could also result in the issuing of a SWO such as where the STMS and/or organisation is unable to or unwilling to voluntarily implement the required corrective actions.

Where a SWO has been issued, the activity/work may not recommence at the worksite until the auditor/reviewer (or appropriately RCA authorised person) is satisfied that the site TTM is appropriately managed and releases the SWO. During the period the SWO is in effect, the contractor may only undertake actions that maintain or improve the safety of the site.

Where no SWO has been issued, all work activity must cease immediately and the TTM be improved to an Acceptable SCR or better as determined by the STMS in consultation with the auditor/reviewer. If the TTM cannot be improved to the required rating, the worksite must be cleared and the road left in a safe condition.

A notice of non-conformance may be issued against the STMS and/or any other responsible party for worksites with an SCR of Unacceptable (Other), Unacceptable, Unacceptable (multiple issues) or Dangerous.

Where there are widespread and/or consistent issues with the TTM provided by an organisation an Organisational NNC may be applied (see E3.6.2 About Org NNC).

It may be necessary to supplement the SCR form with an attached memo or coversheet on which the auditor/reviewer may add additional comments regarding the audit/review.

Where an auditor/reviewer issues a notice of non-conformance a copy of the NNC and of the SCR form must be forwarded to the senior traffic and safety engineer (CoPTTM) for consideration and be recorded in the NZTA's database.

E3.5.5 Non-compliance with TMP principles

Where non-compliance with TMP principles is recorded and forwarded to the contractor (and principal if required) in accordance with appendix C, subsection E3.2 TTM safety audit/review methodology, the contractor must either make prompt changes to address the issues raised or forward reasons why the issues should not be addressed to the TMC within 24 hours.

E3.5.6 Appropriate action for non-complying TTM

E3.5.6.1 If the TTM is being completed under contract

Appropriate action for identified non-complying and/or unsafe TTM may include the following:

- issue a NNC to contractor detailing non-compliance(s) and expected corrective action(s)
- replacement of the contractor's nominated STMS
- arrange for another TTM contractor to make the worksite safe
- apply liquidated damages
- close the worksite down.

E3.5.6.2 If the activity is not being completed under contract to the RCA

Safety standards must still be met. The authorisations for activities on roads must require the appropriate standard for traffic management to be met.

Actions for identified non-compliance may include the following:

- issue an advisory note requiring a corrective action plan
- issue a notice to the person carrying out the activity detailing the noncompliance and expected corrective action
- close down the worksite as an unauthorised worksite
- lay a complaint with the police
- lay a complaint with WorkSafe NZ
- arrange for another contractor to make the worksite safe.

E3.6 Notice of non-conformance

E3.6.1 Who can be issued a notice of non-conformance (NNC)

A rating of Unacceptable (Other), Unacceptable, Unacceptable (multiple issues) or Dangerous is grounds for the issue of a notice of non-conformance.

A NNC can be issued to:

- The STMS and/or delegate in charge of the worksite
- The designer of the TMP

Continued non-conformance from a company/organisation may result in the issue of an organisational NNC (Org NNC).

E3.6.2 About Org NNC

An Org NNC applies if there are widespread and/or consistent issues with the TTM provided by an organisation. The RCA may issue an Org NNC for a one-off incident or for multiple failures.

A 3 strikes approach is used with sanctions being applied if 3 strikes have been issued within 12 months of the issue of the first strike. Strikes 1 and 2 will lapse if no further strike is issued within 12 months of the issue of the first strike.

Any warnings and sanctions may be applied:

- · at the branch level of a company
- within an RCA boundary.

Where subcontractors receive an Org NNC a 'please explain' letter will be sent to the principal contractor asking how they propose to overcome the failure(s).

Appeals may be submitted to the Senior Traffic and Safety Engineer (CoPTTM), NZ Transport Agency National Office, Private Bag 6995, Wellington 6141.

E3.6.3 Org NNC 3 strikes process

The RCA notifies the company/organisation that Strike 1 Org NNC it will be applying a **Strike 1 Org NNC**. Warning Notification is also sent to NZTA. On receipt of **Strike 1 Org NNC**, NZTA registers the event and sends a warning letter to the company/organisation/subcontractor to warn of the consequences of continued non-compliant activity The company/organisation submits a plan to the RCA detailing actions to prevent reoccurrence of the non-compliant activity A similar process is followed for the issue of a Strike 2 Org NNC Strike 2 Org NNC. Final warning On receipt of a Strike 2 Org NNC within 12 months of the issue of the first strike, NZTA sends a final warning letter to the company/organisation/subcontractor also outlining the consequences of continued noncompliant activity The company/organisation submits a plan detailing actions to prevent reoccurrence of the non-compliant activity

Section E - Page 38

Strike 3 Org NNC Apply sanctions

 On receipt of Strike 3 Org NNC within 12 months of the issue of the first strike, NZTA sends a letter detailing the sanctions to be applied and the time period for these sanctions to the branch manager and CEO of the company/organisation/subcontractor. A copy of

Specific NZTA sanctions

 This non-conformance will affect an organisation's NZTA Pre-Qualification status

the letter is also sent to the relevant RCA

 The information will be forwarded to the appropriate standards organisation and may affect the company/organisation's ISO9000 or TQS1 quality rating.

Other sanctions which may be applied by RCAs include but are not limited to the following

- Denied access to the road network for a period of time
- The company/organisation may not be allowed to provide their own TTM for their and their clients worksites and will be required to employ an RCA approved TTM provider for their and their client's worksites on the network for a period of time
- Undergo retraining for CoPTTM warrants

E3.7 Example of site condition rating (SCR) form - full audit/review

ΤΊ	M SITE CON	DITIO	N RATIN	G FOF	RM												
SIT	E DETAILS								OP	ERATIONA	L DETAIL	LS					
RC	A							7 [Ac	tivity descr	iption						
Sub	ourb							7	TT	M method							
Roa	ad name							-	тт	M Contracto	or						
	R/WAP number					Road ID		\dashv \dagger		ntractor- w		1200					
								$\dashv \mid$				acc					
	e/Time					TTM level		_		ent / Princip							
SIG				0:	Weighting	g Tally	y Tota			CELLANEO				1-2-1-1	Weighting	Tally	Total
A1	Missing			Sign	5				E1	Working in			inelle e	Individual Individual	20		
A2 A3	Position Not visible/fallen	ovor		Sign Sign	5				E2 E3	Missing or Safety zon				Individual	10		
A4	Wrong sign	OVEI		Sign	5			_	E4		- '		acceptable	Individual	5		
A5	Condition unacce	eptable		Sign	4				E5				(carriageway	Occasion	15		
A6	Permanent sign			Sign	5			_		only)				0			
A7	Unapproved sign			Sign	4			'	E6	Unaccepta cyclists or o			dition (peds,	Occasion	30		
8A	Non-compliant su	upport / si	ign too low	Support	2	Subto	etal .	-	E7	Barrier defe			r incorrect	Componer	t 10		
MOI		TIC			Mainheim			╛┟		component				Fauinman			
B1	Tail pilot vehicle/		omitted or	Vehicle	Weighting 30	g Tally	y Tota		E8_ E9	Unsafe or I			r inappropriate	Equipmen	t 5 15		
	incorrect location								10	Flashing be	eacons / i		tor lights not	Vehicle	3		
B2	Lead pilot vehicle incorrect location		or	Vehicle	20				11	used or ine Parking / st		eature	s not relocated	Feature	5		
В3	Shadow vehicle of location	omitted o	r incorrect	Vehicle	26			E	12				of plant/equip.	Feature	20		
B4	TMA missing or r	non comp	liant	TMA	26				13	Marginal ite	ems (sign	s, deli	ineators, Hi vis	Feature	1		
B5	AWVMS/arrowbo	ard non	compliant	Vehicle	26			_		gamonto						Subtotal	
_						Subto	otal		DTH	ER WORKS	SITE ASP	ECTS	;				
	ESTRIANS / CYC				Weighting	g Tally	y Tota	<u> </u>	G1	Qualified p	erson on	site [r	efer to A5 of Co	РТТМ]		Yes / Una	cceptable
C1	Inadequate provis	•		Feature Feature	10				G2				C4 of CoPTTM]			Yes / Una	
C2	Inadequate provi	SION TOF C	yclists	reature	10	Subto	otal		G3	Road user					•	Yes / Una	
DEI	.INEATION				Weighting		_	_	G4	On-site red			include STMS a tails1	authority,	2	Yes / Una	cceptable
D1	Missing or ineffec	ctive tape	r	Leading	26	g rung	, Tota		G5	TMP appro			,			Yes / Una	cceptable
D2	Tapers too short			taper Leading	15							Yes / Una	cceptable				
				taper					G7 Approved TMP applicable? Yes / Un								
D3	Taper too short o	r missing		taper	5			_ [G8 TTM in accordance with approved TMP? Yes / Unacc			cceptable					
D4	Spacing in taper			Taper Per 100m	5				FINAL RESULT Score ✓ Rating ✓ Rating								
D5 D6	Spacing along lar Missing or ineffect		neation	Per	3 10			╛	Scc	ore 🗸	Rating	otand	ard (0.10)		ating	otable (51+	only)
	along lanes		leation	section				41	Acceptable (11-25) Unacceptable		otable – Mi	ultiple					
D7	Condition unacce	•		Device	4			$\dashv 1$		⊢	_			, H	(both 51+	and Other A	spects)
D8 D9	Using non-approv			Site	30			\dashv [Needs Improvement (26-50) DANGEROUS Unacceptable - Other (LOW RISK? rat			0)					
D10	level 2 or 3 roads		nness	Access	10			┦┡	A ct	ions planne			ts only)	Sit		ceased by	
- 10	maaaqaatamaa	ng one a	-			Subto	tal			fixed?			es / No	0.0	5 activity	ccasca by	
	Complaint	aallaut?	Sito activit	h, ctatus	Attondo	d/Unattende	Motifica	lion to E) C A	(does not affe	inat anaral	T _V	TMD dos	lan lagı	1002		
	Van /		Site activit Audit/revie	•		d/Unplanne				1? [does not and			es/No TMP des	es / No	LOV RIS		/ No
KE)		INO	Audiblevie	ew .	Flaille	u/Onpiannet	d Good Si	le muuc	liui	i luoes not a	aneci score	9 16	25/NO T	ES / INU	Itio		
AC1	TIONS TO BE TAK	EN															
ALL	NITED / DEVIEWE	D DV -							.01	TMC DETAIL	16						
	DITED / REVIEWE nature	ום ש								TMS DETAIL eceived by /				0	CD loft on	cito2	. ,
	ditor/Reviewer nam	ne						\dashv	⊢	TMS name	oigneu			18	CR left on	SILE! Y	es / No
	alifications	.5			NIZTA	ID No		\dashv	⊢	ualifications				N	ZTA		
Διι	ditor mobile numbe	or .			INZTA	ID No.		\dashv	0.	TMS mobile	number			I	No.		
Au	and mobile mumbe	"							1	vio mobile	HUITIDEI						

In submitting this form, the auditor/reviewer specified above agrees that they have explained the significant issues and proposed remedies to the relevant parties specified above and have provided these parties a physical copy of the audit (does not apply for unattended sites)

E3.8 Full audit/review site condition rating (SCR) - defect descriptions

Multiple deficiencies relating to one item of TTM may only be recorded as a single defect assigned against the rating that is the highest. For example, a sign which is concealed by a tree and is in the wrong position is to be assigned as 'Not visible/fallen over' as this item has a rating higher than the 'Position' item.

E3.8.1 Signs

A1	Missing	Any signs that should have been erected that are missing. A sign and supplementary plate combination is to be counted as one sign eg T1A plus T144. If either the sign or a supplementary plate is missing from a combination when required, then, it is counted as one sign missing.
A2	Position	Any signs where the spacing is too close or too far from other signs or the working space. Refer to CoPTTM worksite layout distance tables. Also includes signs that are too close or too wide apart across the road (eg gated speed signs that are placed on the back berm); signs that are offset by more than the approved allowance (eg TSL signs offset by more than 20m); signs blocking bus stops, cycle lanes or footpaths. Minor amendments should be noted on the TMP. Movement of TSL signs should be notified to RCA to maintain legality.
A3	Not visible / fallen over	Any TTM sign that should be erected at the worksite, which is not visible (eg knocked down or visibility blocked by a parked vehicle, vegetation or street furniture). If obstruction is noted in on-site record and best endeavours have been made, do not include in tally.
A4	Wrong sign	The wrong sign has been used, eg TL2L or TL2R sign showing the wrong lane being closed. Inappropriate signage. Incorrect TSL signage (eg TSL reinstatement incorrect for permanent speed limit). Wrong use of the sign from its intended purpose including detour arrows, NO ENTRY instead of ROAD CLOSED, or use of a sign with similar message but not the correct sign as per CoPTTM definition of use. Non-standard signs should be approved as part of TMP.
A5	Condition unacceptable	Refer to CoPTTM Section C19 Maintenance Standards. Includes signs unreadable at sign visibility distance and graffiti affecting the message of the sign. Marginal signs not included in the tally but must be advised to STMS.
A6	Permanent sign	Permanent signs that have not been covered and are no longer relevant to road users because of the activity. Includes curve advisory if advisory speed higher than TSL (chevron must be left visible), permanent speed limits, permanent lane advisory signs, passing lane advisory signs and permanent signs removed from site to facilitate works but still required. Consider suitability of sign coverage (eg must not affect the reflectivity of the sign when cover is removed). Includes permanent signs blocked by temporary signs. Parking features when relocated but signs not covered recorded under E11.

A7	Unapproved sign used / too small	Signs used that are not approved for use at worksites, includes using level 1 signs at level 2 and 3 TTM worksites. Also includes using signs not approved in TMP (excludes applicable CoPTTM sign where appropriate) and use of a small sign when full sign could be implemented when not approved on TMP or use of small sign in combination with full sized sign (eg small main sign with full size supplementary plate). RD6 sign - CoPTTM does not include use of cone mounted single arrow, twin disc preferred, not counted in SCR but advise TTM provider to phase out use. If smaller sign is required due to environmental factor this should be approved in the TMP.
A8	Non-compliant support / sign too low	Using supports that fail to meet the requirements of subsection B1.3.4 Sign stands and supports. Also includes signs mounted lower than the accepted minimum as described in the CoPTTM, stop/go paddles not in direct physical control by the MTC, attaching a sign to a regulatory sign pole or street furniture where it will cause obstruction or damage to the asset. Also includes signs not being appropriately delineated.

E3.8.2 Mobile & semi static

B1	Tail pilot vehicle / AWVMS omitted or incorrect location	Missing when required or location (lateral or longitudinal) is incorrect. Note: If arrow is incorrect record under E9.
B2	Lead pilot vehicle omitted or incorrect location	Missing when required or location (lateral or longitudinal) is incorrect.
В3	Shadow vehicle omitted or incorrect location	Missing when required or location (lateral or longitudinal) is incorrect. Note: If arrow is incorrect record under E9. When shadow vehicle is missing and requires a TMA record in both B3 and B4.
B4	TMA missing or non compliant	TMA not on mobile operation vehicle(s) when required. TMA is being used correctly but does not meet the certification for compliance as per the test level stated in NCHRP 350 and section B11 Truck mounted attenuators including the tare weight requirements for the vehicle. Crash cushion not deployed when required. Also includes TMA in centre lane with no additional TMAs to close adjacent lanes.
B5	AWVMS / arrowboard non compliant	AWVMS, European arrow board or horizontal arrow board not displaying the correct message (eg the right lane is closed but the arrow is directing traffic to the right). Also includes arrow board not fitted or is not used on mobile operation vehicles when it is required.

E3.8.3 Pedestrians/cyclists

C1 Inadequate provision for pedestrians

Footpath obstructed by activity and neither temporary path nor direction to alternative pedestrian facilities provided. Features (recorded individually) include footpath width, ramps, gradient (including cross fall), visibility, location, any obstructions from exiting environment (low hanging tree branches, street furniture blocking path etc.).

Ramp surface must be non-slip, must not move around and must be of sufficient width. Surface of footpath to be recorded under E6. Signs and delineation for pedestrian management covered under the other relevant sections in A and B.

C2 Inadequate provision for cyclists

Work in a cycle lane or a high cycle use area and temporary facilities for cyclists have not been provided. Features (recorded individually) include cycle lane width, ramps, gradient (including cross fall), visibility, location, any obstructions from existing environment (low hanging tree branches, street furniture blocking etc.). Surface of cycle lane to be recorded under E6. Signs and delineation for cyclist management covered under the other relevant sections in A and B.

E3.8.4 Delineation

D1 Missing or ineffective taper - leading taper (including chicane)

Where leading taper delineation is missing which is required for traffic to shift from normal alignment. If due to environmental factors a short taper is required (but not allowed by the layout distances tables) then it must be included in the approved TMP with appropriate EED and mitigation measures. If 75% of the taper is installed it would be marked as too short rather than ineffective. Any less than 75% installed is ineffective. Also includes if there are too few cones installed to form the taper.

D2 Tapers too short - leading taper Taper has been formed but is too short. CoPTTM requires that two thirds of a taper must be visible. Refer to spacing tables for length requirements.

D3 Taper too short or missing trailing taper Taper has been formed but is too short. CoPTTM requires that two thirds of a taper must be visible. Refer to spacing tables for length requirements.

D4 Spacing in taper

Taper has been formed but spacing of delineation devices is too great (eg 1 to 1.5 x the spacing required in CoPTTM). If more than 1.5 x record under ineffective. Refer to spacing table for requirements.

D5 Spacing along lanes

Delineation placed in rows, which are generally parallel to the centreline, but spacing of delineation devices is too great (eg 1 to 1.5 x spacing required in the CoPTTM). If stop/go centreline delineation is missing record in D6. Refer to spacing tables for requirements. Refer to D6 for ineffective where spacing is greater than $1.5 \, x$ spacing required.

D6 Missing or ineffective delineation along lanes

Where delineation is missing or where the delineation is ineffective at separating lanes or ensuring the road user continues on the desired travel path, misleads traffic or provides conflicting message (eg traffic is required to travel on right but left side appears open and delineation does not effectively keep traffic in the correct lane). Refer to spacing tables for requirements. Refer to D5 for spacing in lanes. **Note:** Requirements for chip seal and paving operations allows double cone spacing.

D7	Condition unacceptable	Refer to section C19 Maintenance Standards, specifically C19.3.4. Includes punctures, large areas of staining, and significant area of missing or stained reflective material. Note : Non-compliant logos may be considered unacceptable if visible to vehicles. Auditor/reviewer to note marginal devices and advise STMS but not include in the SCR result.
D8	Using non- approved device	Delineation or channelling devices that fail to meet the criteria specified in the CoPTTM. Includes marker posts, drums and barriers or other devices used in the place of compliant delineators.
D9	Road marking incorrect at long term level 2 or 3 roads	Road marking not correctly adjusted at long term level 2 and 3 TTM static worksites where alterations are required as part of the approved TMP and other delineation is not implemented. Note: Consider if TTM is applicable for the construction methodology in which case record in "other checks". Where it is not identified in the TMP, a worksite will be considered as long term where the closure is in a continuous configuration for more than 72 hours.
D10	Inadequate / missing site access	Inadequate site access where required as defined in the CoPTTM. No site access visible for level 2 and 3 sites (exception is re-surfacing operations where site access is frequently moved). Site access in poor location. Vehicles accessing site in unapproved manner including against the flow of traffic or impeding traffic flow in unacceptable manner. Signs missing recorded under missing signs. Delineation of site access recorded under D5. Location and spacing of access gap recorded in D10.

E3.8.5 Miscellaneous

E1	Working in live lanes	Personnel associated with the activity are in the live lane outside the established working space and established safety zones. Note: If personnel cross the road without any equipment this is not classified as working in live lane but if carrying or moving equipment/materials from one side of the carriageway to the other, then this is classified as working as their full focus is not on task of crossing road.
		If there is no traffic flowing, then it is permissible for personnel to cross the road (not allowed on a level 3 road). Note: Consider proximity to pedestrian crossing if available but not used. Traffic must not be expected to slow down or stop for personnel to cross the road. If under stop/go operation and MTCs change flow to stop/stop for all traffic approaches then lanes are not to be considered as live. If MTC needs to speak to motorist this should be done via the vehicle passenger side.
E2	Missing or ineffective controller	Manual traffic controller not at stop/go position, footpath controllers not available to manage pedestrian movements where identified as required in the TMP, or spotter not being used when required for inspection activities. Also includes where the MTC is on the right hand

side of approaching traffic rather than the left hand side to stop traffic.

Note: It is acceptable for a cone to be placed in front of the first vehicle provided the MTC remains on the left hand side of the road until the vehicle has come to a complete stop prior to positioning the cone. The cone must only be retrieved whilst the stop paddle remains in place. The MTC must be able to easily reach the paddle if required (eg to prevent the paddle from turning in the wind). If SCR result is High Standard or Acceptable consideration to be given to "road user flow

acceptable" in Other Checks.

E3	Safety zone compromised	Where either the lateral or longitudinal safety zone is insufficient (eg too small or missing). Tally each zone compromised for each occasion whether for plant, materials or personnel. Note: This is not applicable if under a stop/go operation and all traffic flows are on stop.
E4	High visibility garment not acceptable	Refer to section C19 Maintenance Standards, specifically B3, C19.3.6, C19.3.7, C19.4.2 and C19.4.3. Includes garments not done up, torn garments, large areas of staining, and significant area of missing or stained reflective material. Also includes STMS not wearing STMS garment (exception A5.8.7).
E5	Marginal surface condition (carriageway only)	Surface is rough and likely to be dangerous for any type of road user for the temporary or permanent speed limit at the worksite. Marginal to be applied if advised speed on site is 1 step higher than the speed determined by using the TSL decision matrix. Note: If a TSL is not implemented when required due to surface condition, record in this section but if a TSL is implemented when it is not required record in G2. For example, record in E5 as marginal surface condition a 100km/h rural road with chip seal surface not swept with no TSL. Record in G2 a 100km/h rural road with swept chip seal and line marked with 50km/h TSL in place. Also includes steel plates used to protect excavation but not appropriately secured in place.
E6	Unacceptable surface condition (peds, cyclists or carriageway)	Surface is unacceptably rough and likely to be dangerous for any type of road user for the temporary or permanent speed limit at the worksite. Unacceptable if advised speed on site is 2 steps higher than the speed determined by using the TSL decision matrix. For pedestrians and cyclists this includes trip hazards, wet concrete, obstructions, or soft/impaired surfaces (including weather affected).
E7	Barrier defects (missing or Incorrect components)	Includes missing or incorrect end treatments on barriers, non-compliant barriers, end flares too sharp, barrier too close to live lane, barriers not linked, barriers not pinned where required and barrier not used when required. Note: Multiple defects for this item must be counted individually. Also includes device that is being used as a barrier but does not meet the CoPTTM requirements and barriers deployed not in accordance with manufacturer's specifications (eg water filled barriers not filled with water). Component are defined as leading terminal, trailing terminal (if required), flare if not terminal end, barrier alongside work site, linkage of barriers, installation in accordance with manufacturers specifications, damage to individual units (eg Leaking water filled barrier, cracked concrete barrier sufficient to compromise integrity of barrier etc.). Consideration should also be given to the surface the barriers are installed on if the surface would prevent the barrier performing as expected (eg on or in front of a kerb). Delineation of barriers to be recorded under delineation. If barriers not needed but deployed incorrectly record as redundant TTM.

E8	Unsafe or redundant TTM	Redundant TTM to be removed from site if not to be used within 48 hours (eg site reviewed on Friday with signs not required for unattended site stored on site, but further works taking place Sunday night, therefore time between active sites extends past the 48 hours permitted so signs should be removed). TTM equipment stored inappropriately on site when not required for an active closure. Also includes when TTM equipment is stored in front berm, frame and base left upright with sign panel on ground, or frame and base left upright with signs turned to have back panel facing traffic or the sign turned 90° to the travelled path. Includes signs/stands/bases in cycle lanes or footpaths, cones stacked to side not required for unattended sites, TTM equipment left in manner which causes hazard to road user (eg equipment not delineated). Hierarchy for storing TTM equipment: remove from site, then back berm, finally front berm if permanent speed limit is under 65km/h and there is a kerb and channel. Footpaths must not be impacted by the storage of equipment regardless of the width of the footpath available. Storage is only permitted in suburban or commercial areas but not near schools or shopping areas. To be recorded for each sign/stand/base that is unsafe or redundant and once for every 10 delineation devices. Also includes barriers when deployed but not needed.
E9	VMS message incorrect or inappropriate	VMS displaying incorrect messages in relation to activities or VMS board message not approved by RCA.
E10	Flashing beacons / indicator lights not used or ineffective	Amber flashing beacons are not in operation or have been omitted from vehicles where required or do not comply with the CoPTTM requirements. Record in E10 if vehicle indicator lights used in hazard mode to access/exit site. Note: Vehicle indicators should only be used to give direction to road users of a pending site access movement.
E11	Parking / stopping features not relocated	Work encroaches on parking or stopping feature which has not been relocated to a position clear of the worksite. Such features could include bus/transit lane, clearway (during enforceable timeframes), taxi stands, bus stops, bus parking locations, loading zones, mobility spaces and/or drop off areas. This SCR element is different to E12 where the feature is being used to park in but not as part of work site. E11 refers to feature being within work site but not appropriately relocated.

E12 Unsafe and illegal parking of plant / equipment

Plant and equipment is unsafely parked or illegally parked. Includes plant and equipment parked outside of designated work area on footpaths, cycle lanes, broken yellow lines, clearways, bus/transit lanes, bus stops, bus parking spaces, loading zones, taxi stands, mobility spaces, or restricted parking spaces. Also includes plant and equipment on site when unattended and not appropriately protected from public (for example milling machine with no shoulder closure protection). Consideration to be given to the manner in which plant or equipment is parked eg if forcing road user across a centreline. Vehicles must be parked in the direction of traffic flow. Shoulder closures to protect parked plant/equipment must be approved as part of the TMP. Parked plant and equipment must be visible to drivers of vehicles, cyclists and pedestrians so they can see the hazard.

Note: While a vehicle may be legal under the Land Transport Rule to be on the road it may be classified differently under the Health and Safety at Work Act.

E13 Marginal items (signs, delineators, Hi vis garments)

Refer to section C19.3 Evaluation for classification of TTM devices.

Note: Non-compliant logos may be considered unacceptable if visible to approaching road users.

A sign is marginal if there are many surface abrasions throughout the sign face and many are within the individual letters or symbol of the message; the surface is marked by material (such as asphalt, bitumen, cement slurry or dirt) not obscuring the lettering or symbol; some colour fading is evident, the background colour and reflectivity are still apparent; the message is legible and matches the approved design as per section B1 Signs.

A delineator is marginal if the surface is marked by material (such as asphalt, bitumen, cement slurry or dirt) and cannot be readily cleaned; the reflective bands have numerous tears and scratches; the reflective bands are largely free of residue.

A high-visibility garment is marginal if the garment has numerous tears and scratches; the garment has some marks (from materials such as asphalt splattering, bitumen, dirt or cement slurry) and may not be readily cleaned due to abrasion or discoloration. However, it is free of large areas of residue or missing reflective material.

E3.8.6 Other worksite aspects

G1 Qualified person on site [refer to A5 of CoPTTM]

The worksite must be under the control of an STMS or briefed TC for level Low Volume and level 1 sites and an STMS L2/3 Practising or a briefed STMS NP (where allowed) for level 2 and 3 sites. If control of the worksite has been delegated by the STMS, there must be correct documentation of the delegation and or handover including time and briefing. Briefing must include reference to site specific details such as delivery movements or any minor amendments made to the TMP. Delegated STMS-NP/TC must be satisfied with the site condition they are taking responsibility for prior to accepting delegation. STMS delegating the site must ensure that the person they are delegating to is suitably qualified. Auditor/reviewer should allow some flexibility if the physical handover of the site has not been possible, eg if the STMS in control of the site has gone home sick. Auditor/reviewer should allow time for the STMS to be away for auditing purpose (to gain access to the start of the site and while conducting site checks).

G2 TSL appropriate [refer to C4 of CoPTTM]

The TSL must be appropriate in accordance with the CoPTTM TSL decision matrix. The speed limit, including de-restriction, is not appropriate for the physical works or correct for permanent speed limit derestriction. If the TSL is too low (refer to subsection G4.4.6 Excessive or inappropriate use of TSLs), a notice of non-conformance is issued. Consideration should also be given if the speed limit is too high (eg if a 70km/h TSL has been installed however the CoPTTM TSL decision matrix determines a 50km/h is appropriate). Also refer to notes under E5.

G3 Road user flow acceptable

Road users are flowing appropriately through the site; any queues do not extend past first advance warning sign and there are no unreasonable delays or delays in excess of five minutes or durations as approved in the TMP. Unacceptable flows include any instances of vehicular conflict eg two directions of traffic sent on "go" during a stop/go operation or where minimum lane widths are not maintained. G3 can be used to record where access for residents or businesses are not maintained or alternative solutions have not been agreed with the relevant parties, including the RCA.

Note: 5 minute delay is to be in addition to the normal traffic flow on the road for that time period.

G4 On-site record [form must include STMS authority, 2 hourly checks and TSL details]

On-site record available on site which includes information required under the CoPTTM example form.

Note: This does not need to be the CoPTTM form.

Required checks have been conducted in accordance with approved TMP and CoPTTM and are appropriate to the time of the audit/review (eg not completed ahead of the time of the audit/review). Site checks should be robust and provide a high level of confidence in the effective management of the site. Any TSL implementation must be recorded correctly including the installation start time and all individual street names with defined TSL and derestriction sign locations recording where the TSL signs are positioned on that street (eg driveway for a street number or fixed identifying location). If a TSL is not required the STMS should record N/A for the TSL section of the documentation.

G5	TMP approved?	TTM documentation must be at all attended worksites and include TMP proforma, diagrams and other attachments eg the WAP including RCA conditions. Documents must be stamped with the CAR approval stamp and the CAR reference applicable to the TMP must match for all documents. Where applicable documentation must be available for time extensions. Verifiable information is acceptable (eg if approval is via a phone call and there is a record of the date, time and who was involved in the conversation thus allowing confirmation of the approval to take place where required).
G6	Approved TMP sighted?	TTM documentation must be at all attended worksites and include the TMP proforma, diagrams and other associated documents eg the WAP including RCA conditions. A copy of the TMP must be available on site (within 30 minutes of request from auditor/reviewer). Hard copies or electronic copies are acceptable however if using electronic format consideration should be given to a charging device and a mechanism for being able to record information including induction information, on-site record and TSL requirements etc.
G7	Approved TMP applicable?	The approved TMP accurately reflects the road environment including lane configurations, pedestrian features (including signalised crossings, zebra crossings and refuge islands), bus stops, parking features and other site specific features. If not, minor amendments are accurately recorded and notified to the RCA with evidence available of this notification (eg email or phone call with record of who was spoken to, time of conversation and agreed mitigation). Amendments of a significant nature may require submission of a revised TMP for approval. If the TMP is not applicable this is followed up off site with the TMP designer and/or CAR Manager who approved the TMP.
G8	TTM in accordance with approved TMP?	The TTM measures implemented on site match the approved TMP. Minor amendments, as long as they are noted on TMP, with the date, time and signature are acceptable if for reasons of improving road user safety or traffic flow. Minor amendments must not be for benefit of cost or ease of construction. Any significant changes must have been agreed with the RCA and correctly documented and approved (refer G7). Note: Example of an unacceptable amendment being a shoulder closure upgraded to contraflow with no documented evidence of approval. Significant changes must be agreed following consultation with the RCA/TMC/CAR Manager prior to implementation.

E3.9 Example of site condition rating (SCR) form - short audit

SITE CONDITION F							
Street name(s)			RCA p	ermit r	eference		Attended / Unattended
Number (from/to)			Principal				
Employer of site STM	NS		Αι	ıdit con	nmences	am / pm	Date
Rating	A = Acceptable	NI :	= Needs	improve	ment		D = Dangerous
	MARY OF STANDARDS	Α	NI	D		ACTION	NEEDED
1. Responsible party	STMS / TC at attended site? Name: Registration number:						
2. TMP	On site? Appropriate to situation?						
3. High-visibility garments	Worn by all? Done up? Condition acceptable?						
4. Signs	All necessary signs present? Correct positions? Sand bagged for expected wind? Conflicting signs covered? Signs in good condition? Other:				- - - -		
5. Delineation	Protects working space/other features? Taper lengths compliant? Correct spacing of cones? Sufficient positive traffic control? Other:				-		
6. Pedestrian needs	Footpath widths OK? Safe passage for pedestrians? Surfaces / ramps OK? Other:				-		
7. Cyclist needs	Cycle widths OK? Safe passage for cyclists? Surfaces OK? Other:						
8. Traffic needs	Lane widths OK? Speed limit appropriate? No significant delays? Surfaces OK? Other:				- 		
9. Property access	Property access OK?						
10. Site scores	Number in each rating			-			
Action agreed by STMS/TC		Α	NI	D			
Auditor						STMS/TC	
CONTRACTOR COP	(Warrant Number) PY – Hand to contractor once audit has bee	n compl	leted	(Signatur		Audit finished	(Signature) am / pm

E3.10 Examples of ratings (short audit)

EXAMPLES OF RATING	S (SHORT AUDIT)		
ASPECT	A = Acceptable (Standard met)	NI = Needs improvement (Moderate risk)	D = Dangerous (High risk)
1. Responsible party	STMS/TC is at attended site	TC at attended site but STMS arrives after allowed time limit	No STMS/TC at attended site, orNo STMS responsible for the site
TMP (only for attended sites) High-visibility garment	TMP on site, and Appropriate to the situation Worn by all	 TMP on site, and Appropriate to the situation, but There are some safety issues Worn by all, and 	 TMP not on site, or TMP not appropriate to situation Not everyone wearing high-visibility
o. High-visionity guintene	 Done up Condition acceptable 	All high-visibility garments done, and Condition of high-visibility garments marginal	 Rote everyone wearing mgr-visibility garments, or Some high-visibility garments not done up, or High-visibility garments have unacceptable condition
4. Signs	 All necessary signs present Correct order and distances Conflicting signs covered 	Some signs are either missing, of poor quality, or inadequate distance and visibility, but An adequate message given to motorists, or Some conflicting signs not covered, or Some signs not well supported	Some signs are either missing, not visible or conflict with other signs, or blown over, or Motorists are not reasonably warned; causing a hazard to road users
5. Delineation	 Protects working space/other features Taper lengths compliant Spacings of cones close enough Sufficient positive traffic control 	Protects working space/other features but could be better, or Taper lengths should be longer, or Cone spacings need to be reduced, or Not sufficient positive traffic control	Does not protect working space/other features, or Does not provide sufficient positive traffic control
6. Pedestrian needs	 Footpath widths OK Surfaces and ramps in place Appropriate protection provided 	Safe passage for pedestrians but footpath width could be greater, ramps and surfaces could be better, entry point could be more obvious	Insufficient footpath widths, or No safe passage for pedestrians, or Surfaces not suitable for pedestrians, or Pedestrians forced onto road close to fast traffic or past a dangerous site without sufficient protection Pedestrians not using option provided
7. Cyclist needs	Cycle widths OKSurfaces OKSafe passage provided	 Safe passage provided for cyclists, but Widths need to be greater, or Surfaces need to be better, or Signage more appropriate 	 Cycle widths not acceptable, or No safe passage for cyclists provided, or Surfaces not suitable for cyclists, or No positive traffic management to enable cyclists to merge
8. Traffic needs	 Sufficient lane widths OK Speed limit appropriate No significant delays Surfaces OK 	Lane widths not narrow enough for positive traffic management needs, or Too narrow and causing a nuisance, or Some unnecessary delays Surfaces rough and uneven	 Lane widths causing hazard by failing to positively control traffic, or Speed limit not appropriate to site, or Surfaces unacceptably rough
9. Property access	Occupants well catered for and informed	Some minor access difficulties	Serious access difficulties

E4 Appendix D: Measure and payment for traffic management (guidelines only)

E4.1.1 Installation, uplift and removal

Payment will be made on a lump-sum basis for the following:

- Preparation and approval of the TMP, and all advertising and notifications necessary.
- Establishment on worksite of all vehicles, equipment, materials and personnel sufficient to undertake the installation of all traffic management as per the approved TMP.
- Establishment on worksite of all vehicles, equipment, materials and
 personnel sufficient to undertake the uplifting and reestablishment of
 any traffic management measures required as part of the changing road
 works operation throughout the project.
- Establishment on worksite of all vehicles, equipment, materials and
 personnel sufficient to remove all traffic management measures on final
 completion as per the approved TMP, and leave the worksite in an
 equivalent or better condition than originally.

Fifty percent of the lump-sum payment will be made on successful installation of the first phase of the TMP. The remaining payment will be made on completion of all traffic management activities and tidy up of the worksite.

E4.1.2 Maintenance of the TTM

Payment will be made on a daily basis for the duration of the traffic management services. This payment must cover all costs associated with:

- the daily maintenance of conforming traffic management at the
 worksite including the supply of all vehicles, equipment, materials and
 personnel sufficient to maintain the traffic management measures as
 specified in the accepted TMP
- inspections and maintenance of quality assurance records
- any other costs associated with traffic management on site that have not otherwise been allowed for.

There will be no payment for any day or days when traffic management occurs on worksite that does not conform to the approved TMP.

Non-conforming traffic management is deemed to occur when signs, delineation devices and/or any other traffic management equipment are not positioned or used as required by the accepted TMP for any period exceeding the inspection cycle as specified in subsection C19.5.1 Monitoring frequency for TTM measures.

E5 Appendix E: Newspaper advertisement standard

Advert format to be as follows:

Width: Double column

On top: Road controlling authority logo

Title: Brief description of the activity

Wording '(RCA) wishes to advise that, weather permitting,

(if appropriate) the (local description of affected road including start and finish points if necessary) will be

closed between the hours of (time format to be 9.00

am) and

(time format to be 7.00 pm) on (date format to be 11 April 2012) for

(brief description of activity).

Where activity could be delayed the following provision may also be added:

However if (give reasons for possible delay) prevents activity at these times, the activity will be carried out on the next available day/night (give alternative dates and times as detailed above) road users are requested to follow the sign posted detours whilst the closure is in operation.

(RCA) regrets any inconvenience caused.

(Name of RCA representative)

E6 Appendix F: Example of notice of non-conformance

NOTICE OF NON-CONFORMANCE							
Date of audit	Time						
Audited by	of						
Contractor	Contract/consent number						
STMS/Responsible parties:							
This notice is to inform you that the temporary traffic management at the management practices:	he following worksite is not in	accordance with accepted traffic					
Roads:							
Location:	RS:	RP:					
 STMS nominated in TMP not on worksite TC nominated in TMP and briefed by STMS (level LV and level 1) r Copy of signed and approved TMP not on worksite Safety audit of temporary traffic management site condition rating 'c Temporary traffic management not in accordance with the CoPTTM Inappropriate or excessive TSL The details of non-conforming temporary traffic management are: The actions required to be implemented are:	dangerous'						
Notice handed / mailed / faxed (delete those that do not apply) to							
	on at						
Note: For attended sites, notification must be given to the site STMS or I	C before auditor leaves the wo	orksite					
Signed:	Received:						
Engineer:	Contractor:						

E7 Appendix G: Example of notification of road closure/lane closure of state highways/local authority road

NOTIFICATIO	N OF ROAD CLOSU	RE/LANE CLO	SURE OF	STATE	HIGHWAYS/LOCAL	AUTHORI	TY ROADS	
RCA					Road/State highway			
Locality						RP		
Closed at		am / pm	Date					
Reason (add	Yes as appropriate)							
Snow	Drop o	ut	V	/ehicle b	olockage/crash		Fatal crash	
Ice	Wash	out	Т	oxic spi	II		Planned closure	
Slip	Floodii	ng						
Other:								
Estimated du	ration closure (add)	es as appropr	iate)					
<2 hours		<12 hours						
<6 hours		>12 hours (se	ee below)					
Closed by (ad	dd Yes as appropriate)						
Police	Fire Se	ervice						
RCA	Other							
Alternative ro	ute/s available and	conditions tha	nt apply					
Reporting off	icer							
For closures	>12 hours AND cras	hes/spills						
Open at:	am / pm	Date:						
Remaining res	strictions:	No / Yes	s (specify):					
Work outstand	ling:	No / Yes	s (specify):					
Reporting office	er:				m closed: d carriageways only)			
Head Office u	se only: cc							
HCM CE	File							

E8 Appendix H: (Ex-LRS - only applies to STMS-delegated authority to self-approve) Example of application for delegated authority to approve TMPs for selected level LV and level 1 roads

	APPLICATION FOR DELEGATED AUTHORITY TO APPROVE TMPS FOR SELECTED LEVEL LV AND LEVEL 1 ROADS (Ex LRS – only applies to STMS delegated authority to self-approve)							
To the traffic m	anagement coordinator							
RCA name		Date						
RCA address								
	oly with the requirements of the CoPTT the manner outlined in the CoPTTM.	M and I apply for delegated authority to approve TMPs on I	RCA selected level LV and					
Signed by								
oigned by	Signature	Full name						
STMS ID								
number	ID number	Expiry date (CoPTTM qualification expiring)						
	Name							
Company								
, ,	Postal address							
	, , , , , , , , , , , , , , , , , , ,	After hours contact details						
Road controlli	ing authority response (should dele	gation be considered appropriate)						
	agement coordinator hereby delegates d requirements set out in the CoPTTM.	s the power to approve traffic management plans and TSLs	in accordance with the					
Please note that	at TMC approval is still required for:							
repeated i		A7.2.1 STMS delegated authority – situations for TMC appropriate the level LV and level 1 TTM handbook) and the following	•					
2.								
3.								
The delegation	of this power must only continue in eff	fect while you remain in the employment of the above Comp	pany or until:					
1. Your STM	S qualification expires, or is withdrawr	n as a result of non-conformance, or						
2. The RCA	specifically revokes this delegation, or							
3. yea	ars from the date of this delegation (to	a maximum of 5 years), or						
4. (da	ate to be entered by TMC no more than	n 5 years from date of this delegation), whichever is soonest	t.					
Signed by								
-19.104.07	Signature	Full name	Date					
On behalf of								
	RCA name							

E9 Appendix I: (Ex-LRS – only applies to STMS-delegated authority to self-approve) Example of application for traffic management coordinator's (TMC) approval of traffic management plan (TMP)

APPLICATION FOR TRAFFIC MANAGEMENT COORDINATOR'S (TMC) APPROVAL OF TRAFFIC MANAGEMENT PLAN (TMP) (Ex LRS)							
This is a cover letter exp	plaining why a TMP is submitted for appro	val. Behind this form attach a TMP	form. Also in	clude any s	site specific layout drawings.		
TO							
RCA name				Date			
From							
Company							
Return address							
Email			Fax				
TMP form attached	Yes / No						
Site specific layout dr	awings attached (Please provide a se	parate reference numbers/name	es for each	page atta	ched) Yes / No		
Number of pages atta	ached:						
	traffic management plan is needed for has been requested by the RCA as p	• , ,	appropriate	options v	vith an X)		
A STMS	person with delegated authority is not	available within the organisatio	n to approve	e the plan			
There is	no TMD in the level LV and level 1 har	ndbook to represent the worksit	е				
	eeds to be closed or traffic delays for r outes in any 1 hour period (except whe			the day o	or for a cumulative period		
A footpat	h will be closed and users will have to	cross a live lane					
A cycle la	ane will be closed						
A pedest	rian crossing or traffic signal installation	n is affected					
Restricte	d parking, bus stop, loading zones and	d/or taxi stands will be affected					
Portable	traffic signals are to be used						
State mo	del details (maker and model descript	ion/number):					
A lane clo	osure is required at an intersection						
Signs ne	ed to be placed on a flush median						
Traffic me	oving in one direction is split around a	closure					
Mobile or	perations are on roads with posted spe	eed limit exceeding 50km/h (exc	cept for grad	ding opera	itions)		
The activ	ity is an event						
Other:							
Comments							
road environment. An It is the responsibility affect the safety of this		nation is the responsibility of the	applicant.		•		
STMS/Applicant sig	nature						
Signature		Full name					

E10 Appendix J: (Ex-LRS - only applies to STMS-delegated authority to self-approve) Database to record delegations to STMS

A Microsoft Excel spreadsheet using these column headings is available on the NZTA's website.


The list below details personnel who are permitted to approve TMPs on roads within (*name RCA road network*) that are designated as levels LV and 1, and where the exceptions listed in subsection A7.2.1 STMS-delegated authority – situations for TMC approval and any additional conditions set out in the (*name RCA*) TTM operating manual (*refer to page*) do not apply. The delegation is conditional on the following:

- The STMS remaining in the employ of the employer named below.
- The STMS maintaining his/her qualification in accordance with CoPTTM where the period extends beyond their qualification expiry date.
- The authority given to the STMS not being revoked by (name RCA).
- The STMS developing the TMP.
- The STMS being paid by his/her employer to develop, consider and approve the TMP, and
- The STMS's employer having current professional indemnity insurance in place to indemnify the RCA of consequent actions arising from the approval of the TMP to the value of \$X,XXX,XXX (RCA to complete) except as required by New Zealand law.

Name	ID	Qualification	Expiry date	Employer	Contact details (including after hours contact)	Authority granted on	Period (years)	Authority expires
Example - Joe Bloggs	100000	L1 STMS	10/1/11	ABC Contractors Ltd	027 432XXXX	11/1/11	4	10/1/16

E11 Appendix K: Report on incident at roadworks site

Reporting company reference:					CoPTTM.Inc	CoPTTM.Incident reference:				
Reference added by re	porting compar	ny			Reference a	Reference added by the CoPTTM.Incident database administrator				
REPORT ON INCI	DENT AT R	OADWO	RKS SITE							
Send to: CoPTTM.	Incident@nz	ta.govt.n	z and the RCA	A in char	ge of the networ	rk (includ	ling NZ	ZTA for state high	hways)	
Date of incident					Time of incident					
Reported by					Company					
STMS name					STMS No.					
Contractor /TTM Company					Contact number					
Road location (include direction and lane)										
Description of work being undertaken										
Incident type	Near m	iss	Vehicle ent	tered Vehicle entered working space				TMA hit	Other	
Operation type	Statio	C	Mobile	•	Semi-stat	tic	Shoulder		Unattended	
		Install		Stat	tic, mobile, se	mi stat	io		 Removal	
Phase of operation		IIIStaii		Siai	iic, iiiobiie, se	:IIII-Stat	il		Kemovai	
		Vehicles	•		Plant			TTM equipment		
Damage to		Vernoice			Tiunt			1110	Годирион	
	Number of people		e number of peo ch injury categor		Minor		No	tifiable	Fatal	
Injuries	in each injury	R	oad workers	5						
	category	ı	Road users							
Crash code	From	Append	ix 1 attache	d	Road user	Ve		e/road user type	Reg. number	
If TMA hit, which TMA					Which lane					
Police attended	(Officer name/number)				Further information	For	a mo	re detailed inte	rnal report (contact)	
Description of events				·		_				







Appendix 1: Vehicle movement coding sheet

	TYPE	Α	В	С	D	Е	F	G	0
Α	OVERTAKING AND LANE CHANGE	PULLING OUT OR CHANGING LANE TO RIGHT	HEAD ON	CUTTING IN OR CHANGING LANE TO LEFT	LOST CONTROL (OVERTAKING VEHICLE)	SIDE ROAD	LOST CONTROL (OVERTAKEN VEHICLE)	WEAVING IN HEAVY TRAFFIC	OTHER
В	HEAD ON	ON STRAIGHT	CUTTING CORNER	SWINGING WIDE	BOTH OR UNKNOWN	LOST CONTROL ON STRAIGHT	LOST CONTROL ON CURVE		OTHER
С	LOST CONTROL OR OFF ROAD (STRAIGHT ROADS)	OUT OF CONTROL ON ROADWAY	OFF ROADWAY TO LEFT	OFF ROADWAY TO RIGHT					OTHER
D	CORNERING	LOST CONTROL TURNING RIGHT	LOST CONTROL TURNING LEFT	MISSED INTERSECTION OR END OF ROAD					OTHER
Е	COLLISION WITH OBSTRUCTION	PARKED VEHICLE	CRASH OR BROKEN DOWN	NON VEHICULAR OBSTRUCTIONS (INCLUDING ANIMALS)	WORKMANS VEHICLE	OPENING DOOR			OTHER
F	REAR END	SLOWER VEHICLE	→ → ↑↓ CROSS TRAFFIC	PEDESTRIAN	→ → → QUEUE	SIGNALS T	\rightarrow Δ		OTHER
G	TURNING VERSUS SAME DIRECTION	REAR OF LEFT TURNING VEHICLE	LEFT TURN SIDE SIDE SWIPE	STOPPED OR TURNING FROM LEFT SIDE	NEAR CENTRE LINE	OVERTAKING VEHICLE	TWO TURNING		OTHER
Н	CROSSING (NO TURNS)	RIGHT ANGLE (70° TO 110°)							OTHER
J	CROSSING (VEHICLE TURNING)	RIGHT TURN RIGHT SIDE	OPPOSING RIGHT TURNS	TWO TURNING					OTHER
K	MERGING	LEFT TURN IN	RIGHT TURN IN	TWO TURNING					OTHER.
L	RIGHT TURN AGAINST	STOPPED WAITING TO TURN	MAKING TURN						OTHER
М	MANOEUVRING	PARKING OR LEAVING	"U" TURN	"U" TURN	DRIVEWAY MANOEUVRE	ENTERING OR LEAVING FROM OPPOSITE SIDE	ENTERING OR LEAVING FROM SAME SIDE	REVERSING ALONG ROAD	OTHER
N	PEDESTRIANS CROSSING ROAD	LEFT SIDE	RIGHT SIDE	LEFT TURN LEFT SIDE	RIGHT TURN RIGHT SIDE	LEFT TURN RIGHT SIDE	RIGHT TURN LEFT SIDE	MANOEUVRING VEHICLE	OTHER
Р	PEDESTRIANS OTHER	WALKING WITH TRAFFIC	WALKING FACING TRAFFIC	WALKING ON POOTPATH	CHILD PLAYING (INCLUDING TRICYCLE)	ATTENDING TO VEHICLE	ENTERING OR LEAVING VEHICLE		OTHER
Q	MISCELLANEOUS	>+0/ FELL WHILE BOARDING OR ALIGHTING	>O/ FELL FROM MOVING VEHICLE	TRAIN	PARKED VEHICLE RAN AWAY	EQUESTRIAN	FELL INSIDE VEHICLE	TRAILER OR LOAD	OTHER

New Zealand Government

st = Movement applies for left and right hand bends, curves or turns

E11.1 Appendix K: Guidelines for completion of Report on incident at roadworks site

Reporting company reference: Reference Number which associates this report to an internal Job number/Contract number/Incident number	CoPTTM.Incident reference: NZTA OFFICE USE ONLY
Reference added by reporting company	Reference added by the CoPTTM Incident database administrator

REPORT ON INCIDENT/CRASH AT ROADWORKS SITE Send to: CoPTTM.Incident@nzta.govt.nz and the RCA in charge of the network (including NZTA for state highways) This is the date of the incident/crash This is the time of the incident/crash NOT the Time of Date of NOT the date when this form is date when this form is completed. If no-one on completed site to record the time, please state this was the incident incident This is the name of the person who This is the name of the company who was has access to all of the details of the directly involved with the incident/crash: incident/crash and is completing this The owner of the worksite The owner of vehicle/plant involved Reported by Company The employer of the person or persons involved If sub-contractor to main contractor give both names and identify which was directly involved Give the full name of the STMS in Give the CoPTTM ID number of the STMS in STMS name charge of the TTM at the worksite at STMS No. charge of the TTM at the worksite at the time of the time of the incident/crash the incident/crash Give the name of the company/ Give the telephone contact number(s) for the company/contractor carrying out the work contractor carrying out the work activity within the working space Contractor activity within the working space Contact Give the name of the TTM contractor Give the telephone contact number(s) for the number /TTM Company supplying the TTM at the time of the TTM contractor supplying the TTM at the time of incident/crash the incident/crash Wherever possible give GPS positioning of the worksite/incident/crash Road location Give the name of the road on which the incident/crash happened and the name of any side road(s) (include affected by the incident/crash direction and Give the suburb and region of where the road is located lane) Identify the direction of travel and the lane(s) vehicle(s) were travelling in prior to the incident/crash Describe the work activity being carried out, and how the road environment was affected by the work activity and installed TTM at the time of the incident/crash Attach a copy of the TMP being used at the time of the incident/crash to this form when submitted Attach a copy of the On-Site Record being used at the time of the incident/crash to this form when submitted Attach a copy of the Hazard ID form being used by the working space contractor at the time of the **Description of** incident/crash to this form when submitted work being Attach photographs of the worksite layout showing all TTM equipment installed at the time of the undertaken incident/crash to this form when submitted Attach a drawing of the worksite layout showing all TTM equipment installed at the time of the incident/crash and the position of the vehicle(s)/road users involved to this form when submitted If a video is available of the incident occurring or of the incident/crash site following the incident/crash then include when the form is submitted – NOTE the video is not to replace the required photographs **Near miss** Vehicle entered Vehicle entered TMA hit Other Incident type TTM working space

Operation type	Indicate eith YES or NO further deta be given be Description events box Statio Confirm if the operation a time of the incident/craft.	- iil to elow in of CC hee t the	Indicate either YES or NO-further detail given below Description events box Mobile Confirm if the operation at time of the incident/cras	I to be in of	Indicate either Y or NO – further detail to be given below in Description of events box Semi-static Confirm if the operation at the time of incident/crash w	n ;	Indicate either YES or NO – further detail to be given below in Description of events box Shoulder Confirm if the operation at the time of the incident/crash was a TTM Shoulder		Indicate either YES or NO – further detail to be given below in Description of events box Unattended Indicate either YES or NO – further detail to be given below in	
	was Static		was Mobile	I	Semi- Static TTI		closi	ure	Description of events box	
Phase of operation	Indicate eith further deta in Descripti	il to be	S or NO – given below	Indica furthe	tic, mobile, sem ate either YES or N er detail to be given scription of events	VO – n belo		Removal Indicate either YES or NO – further detail to be given below in Description of events box		
	,	Vehicle	es		Plant			TTM	l equipment	
Damage to	Indicate eith further deta in Descripti	il to be	given below	furthe	ate either YES or Ner detail to be given scription of events	n beld	ow		er YES or NO – to be given below in of events box	
		Enter the number of peo each injury categor			Minor		Notifiable		Fatal	
Injuries	Number of people in each		s	Confirm the number of persons injured			the number as injured	Confirm the number of persons injured		
	injury category Road users				Confirm the number of persons injured		Confirm the number of persons injured		Confirm the number of persons injured	
	From A	From Appendix 1 attached						/road user type	Reg. number	
Crash code	Use the associated coding sheet to confirm type of crash				Road user		Give the type of road user i.e. car; truck; motorbike; bus; cycle; pedestrian		Give registration numbers of all vehicles involved	
If TMA hit, which TMA	relation to a any installe	any othe d TTM s used a	f the TMA in er TTM vehicle signs or electr t the time of th	onic	Which lane	in a was Cor in r	Confirm which lane the TMA was operating in and where the work vehicle/work activity was being carried out Confirm the position of the Tail pilot vehicle, in relation to the TMA that was hit, at the time of the incident/crash			
Police attended	YES then g officers' nan contact deta	ive the i me/num ails ava	ner YES or NC in charge Poli ber and any ilable – mobile ess	ce	Further information	If there is to be more information added or is available through another source, then give the name and contact details – mobile number/email address - of the person to contact for that further information				
Description of events	Where you have indicated YES in any of the boxes above give further details to confirm and collaboration Explain your understanding of what happened or what you witnessed of the incident/crash. If you had other company forms to assist you with recording the detail, then attach that form to this form as your explanation						nt/crash. If you have this form as your ch information as you the development of			