



Waihi to Omokoroa

SAFETY IMPROVEMENTS

What to expect during construction



We'll focus on ensuring two lanes are open for traffic, unless it's not practicable or safe, and residents and road users know in advance when work is happening.

We've split the project into 10 sections to help limit the number of roadworks that people encounter along the highway.

Section by section, we'll locate services and move if required, and clear trees and vegetation. In some locations, fences inside the road boundary will be relocated. Where the road is being widened, we'll remove the roadside topsoil and bring in extra material. Some drains will be installed, and chip seal will be laid. Once this is completed, safety barriers will be put in, followed by line marking, including the wide centreline.

You may experience some minor delays because of the work, and we appreciate your patience.

Each section will take between 12-18 months to complete. The project is expected to be finished in 2023.

nzta.govt.nz/w2o